

T9S, R93W, 6th P.M.

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELLHEAD.
- = TOP OF GAS & TARGET BOTTOM HOLE.
- ▲ = SECTION CORNERS LOCATED.

1997 Alum. Cap
#12093, 0.4' High
Lat: 39.269580°
Long: -107.792907°

Set Marked Stone,
Steel Post
Lat: 39.269605°
Long: -107.783787°

2007 Alum. Cap
#17492
Lat: 39.269607°
Long: -107.802288°

N89°46'04"W - 2657.08' (Meas.)

S89°48'48"W - 2583.18' (Meas.)

**GUNDERSON BCU
20-08E**

1032' FNL 1985' FWL
Fin. Pad Elev = 7145.2'
Lat: 39.266756°
Long: -107.795281°

N00°00'03"E - 5215.71' (Meas.)

S86°36'07"E
2124.13'

Top of Gas &
Target Bottom Hole
1877' FNL 1296' FEL
Lat: 39.264441°
Long: -107.788397°

20

N00°19'14"E - 2590.31' (Meas.)

2008 Alum. Cap
0.2' High
Lat: 39.262496°
Long: -107.783836°

N00°09'25"W - 2593.07' (Meas.)

2007 Alum. Cap,
#17492, 0.7' High,
Steel Post
Lat: 39.255294°
Long: -107.802283°

S89°40'17"W - 5232.99' (Meas.)

Set Marked Stone,
E-W Fenceline
Lat: 39.255381°
Long: -107.783811°

NOTE DISTANCE TO NEAREST:

BUILDING: N12°W 1151'
BUILDING UNIT: N15°W 1152'
HOBUS: OVER A MILE
DOAA: OVER A MILE
PUBLIC ROAD: NORTH 1219'
ABOVE GROUND UTILITY: N03°W 1232'
RAILROAD: OVER A MILE
PROPERTY LINE: SOUTH 265'

NOTE:

- 1.) All latitudes and longitudes are given in NAD 83 coordinates.
- 2.) Distances to nearest section lines are measured perpendicularly.

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



REGISTERED LAND SURVEYOR
REGISTRATION NO. 38130
STATE OF COLORADO 08-25-17

PDOP = 1.4



REV: 2 01-21-17 S.S. (BOTTOM HOLE MOVE)

BASIS OF BEARINGS
BASIS OF BEARINGS IS A G.P.S. OBSERVATION

BASIS OF ELEVATION
BENCH MARK (19 RDS) LOCATED IN THE SE 1/4 OF SECTION 16, T9S, R93W, 6th P.M., TAKEN FROM THE SOUTH MAMM PEAK, QUADRANGLE, COLORADO, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 7252 FEET.



LARAMIE ENERGY, LLC

**GUNDERSON BCU 20-08E
NE 1/4 NW 1/4, SECTION 20, T9S, R93W, 6th P.M.
MESA COUNTY, COLORADO**

| | | | |
|-------------|------------------|----------|------------|
| SURVEYED BY | BRADEN BOX, B.B. | 08-19-15 | SCALE |
| DRAWN BY | S.S. | 10-20-16 | 1" = 1000' |

WELL LOCATION PLAT



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017