



01445666

RECEIVED

MAY 16 05

## RED WILLOW PRODUCTION COMPANY

COGCC

**Well History:**

Well Name: Dow# 41-33

09-27-03: Mid Continent Energy Rig #1 rigged up  
 09-28-03: Spud well  
 10-09-03: Drilling Rig tear down

10-22-03: RU Brandex Wireline Unit  
 10-31-03: Dakota perf'd 7202'-7227'  
 12-04-03: Dakota frac'd  
 12-15-03: Dakota was determined to be uneconomic RDMO Swab rig

01-09-04: MIRU Key #216, Dakota plugged (CIBP @ 7150' on 1-12-04)  
 01-12-04: J-Sand perf'd 6914'-6924', 6932'-6944', 6948'-6980'  
 01-13-04: J-Sand frac'd  
 01-14-04 to 01-30-04: Well swabbed with water produced and very little gas.  
 Gas starts flowing on 30th, swabbing rig released.  
 02-03-04: Turned well over to production

07-20-04: Codell perf'd 6459'-6470'  
 07-22-04: Codell frac'd  
 07-27-04: Niobrara perf'd 6295'-6304', 6350'-6355'  
 07-29-04: Niobrara acidized w/ 15% HCL and frac'd

08-21-04: Turned well over to production (Codell, Niobrara, and J-sand  
 Commingled)

8-5/8" 24# J55 Surface Casing @ 410'.  
 Cmt'd w/285 sks

Tbg: 220 jts 2-3/8" 4.7# 8rd EUE Tbg  
 Seating Nipple (1.10')  
 Pump off bit sub (1.0')  
 EOT at 6907' KB

Niobrara: Perf'd: 4 SPF, 56 holes, 0.33" EHD (7/27/04)  
 6295'-6304'  
 6350'-6355'  
 Frac'd: Acidized w/ 15%HCL, 180.4M lbs 20/24 sand (7-29-04)

Codell: Perf'd: 4 SPF, 44 holes, 0.38" EHD (7/20/04)  
 6459'-6470'  
 Frac'd: w/172.8M lbs 20/24 sand (7-22-04)

J-Sand: Perf'd: 2 SPF, 108 holes, 0.43" EHD (1/12/04)  
 6914'-6924'  
 6932'-6944'  
 6948'-6980'  
 Frac'd: w/488.1M lb 20/24 sand and 12M lb 12/20 AcFrac CR (1-13-04)

CIBP set @ 7150', 1sck cement & 1sck sand

Dakota: Perf'd: 4 SPF, TCP, Underbalanced (10/31/03)  
 7202'-7227'  
 Frac'd: w/47.3 M lb 20/24 sand and 8M lbs AcFrac Blac (resin)  
 All sand with Sand Wedge added. (12/04/03)

PBTD 7368'  
 TD 7375'

168 Jts 4-1/2", 11.6#, Limited Service LTC Casing  
 Float Shoe @ 7371'  
 Cmt'd w/372 sks. CBL TOC = 5910'

**WELL INFORMATION**

<b>WELL NAME</b>	DOW #41-33
<b>PROPERTY #</b>	01279
<b>DATE (WBD updated)</b>	4/20/2005
<b>API #</b>	05-123-21329-00
<b>STATUS</b>	Producing
<b>SURFACE LOCATION</b>	T5N-R63W SECTION 33 830' FNL 652' FEL, NENE
<b>BOTTOM-HOLE LOCATION</b>	T5N-R63W SECTION 33 830' FNL 652' FEL, NENE
<b>COUNTY, STATE</b>	WELD COUNTY, COLORADO
<b>GROUND ELEVATION</b>	4533'
<b>KB-GR MEASUREMENT</b>	10' (KB =4543')
<b>COMMENTS</b>	J-sand, Codell and Niobrara Commingled