

PxA Wellbore Diagram

Best Information as of 1/31/17

Elev. GL: 4686'
KB: 4696'

Spud: 5/3/2000
Comp: 6/17/2000
PxA'd: 1/11/17

8-5/8", 24#
Set @ 305'

15 sx cement plug at surface

Cemented from 355'-255' w/50 sx
Shot 4 sqz holes @ 355'

50 sx Csg Plug 350' to 250'

Cemented from 1300'-1500' w/40 sx

Cement Retainer @ 1400'
Shot 4 sqz holes @ 1500'

Top of Cement @ \pm 5580'

Hole size 7-7/8" to TD

Niobrara Top @ 5870'

Production Casing
5-1/2" 17# J-55
set @ 6739' w/160 sx

20 sx cement plug @ 5850'-5750'

Set CIBP @ 6525' w/10 sx cmt on

6584' perforated w/4 SPF

6588'

PBTD @ 6739'

TD: 6765'

Markus Production, Inc.
Wickstrom #33-16

NW/SE Section 16-T6N-R60W
Morgan County, Colorado
API# 05-087-08117