



SRC ENERGY

Operator: SRC Energy
Well Name: Bowen #25-10
Legal: NWSE, Section 25, Township 4N, Range 67W
Location: Weld County, CO
API: 05-123-14268
Surface: 8.625" 24# @ 265' **Hole Size:** 12.25" **TOC:** Surface
Production: 4.5" 11.6# @ 7,434' **Hole Size:** 7.875" **TOC:** 6,210 (CBL)
Perforations: 6,976' – 6,980' (Niobrara)
7,044' – 7,048' (Niobrara)
7,070' – 7,084' (Niobrara)
7,267' – 7,287' (Codell)
TD: 7,454'

P&A Procedure

1. Conduct pre-job safety meeting and complete daily JSA
2. Blow down well if necessary, circulate hole with treated water
3. Dig out around wellhead and check surface annulus for pressure
4. MIRU WO unit, ND wellhead, NU BOP, tally all pipe
5. TIH w/ 4-1/2", 11.6# retainer, set at 6,901' and squeeze perfs (50 sxs)
 - a. Release off of retainer and pump 5 sx on top to create 50' plug
 - b. TOOH
6. Pressure test csg to 500 psi for 15 minutes
7. Cut 4.5" @ 275', and POOH
8. TIH to 325' and pump a 325' shoe plug (0' – 325')
 - a. 135 sx of 15.8# class G neat 1.15 cu./ft. yield cement, (325' – 0')
 - b. 60' out of surface casing
 - c. Wait 4 hours and tag plug
9. RDMO WO unit
10. Dig up wellhead and cut off 10' below restored ground level, top off if necessary
11. Weld on cap with ID plate, inscribed with well location, and identity
12. Backfill, clean location
13. P&A complete