



# Job Summary

Ticket Number  
TN# FL1527

Ticket Date  
3/13/2017

COUNTY	COMPANY	API Number
Weld	Ensign Drilling	05-123-23603
WELL NAME	RIG	JOB TYPE
Wolfrum 32-10	Ensign 354	Stub Plug
SURFACE WELL LOCATION	O-TEX Field Supervisor	CUSTOMER REP
SWNE 10 6N 64W	Joyner, Barlen	Mr. Eloy Cossio
EMPLOYEES		
	Forsyth, Scott	
Svoboda, Milo		

## WELL PROFILE

Max Treating Pressure (psi):	Bottom Hole Static Temperature (°F):	100
Bottom Hole Circulating Temperature (°F):	Well Type:	Oil

## Open Hole

1	Size (in)	TMD From (ft)	TMD to (ft)	TVD From (Ft)	TVD to (Ft)
	9	576	1100		
2	Size (in)	TMD From (ft)	TMD to (ft)	TVD From (Ft)	TVD to (Ft)

## Casing/Tubing/Drill Pipe

Type	Size (in)	Weight (lb/ft)	Grade	TMD From (ft)	TMD to (ft)	TVD From (Ft)	TVD to (Ft)
Surface	8.625	24		0	576		
Type	Size (in)	Weight (lb/ft)	Grade	TMD From (ft)	TMD to (ft)	TVD From (Ft)	TVD to (Ft)
Production	4.5	10.5		1100	1165		
Type	Size (in)	Weight (lb/ft)	Grade	TMD From (ft)	TMD to (ft)	TVD From (Ft)	TVD to (Ft)
Tubing	2.375	4.7		0	1165		

## CEMENT DATA

Stage 1: From Depth (ft): 0 To Depth (ft): 1165  
Type: Stub  
Volume (sacks): 450 Volume (bbls): 92.2

Cement & Additives:	Density (ppg)	Yield (ft³/sk)	Water Req.
100% Class G	15.8	1.15	5.00

## SUMMARY

Preflushes:	10 bbls of Mudflush	Calculated Displacement (bbl):	Stage 1 0.5	Stage 2
	3 bbls of Fresh Water	Actual Displacement (bbl)	0.5	
	bbls of			
Total Preflush/Spacer Volume (bbl):	13	Plug Bump (Y/N):	N/A	Bump Pressure (psi): N/A
Total Slurry Volume (bbl):	86	Lost Returns (Y/N):	N (if Y, when)	N/A
Total Fluid Pumped	99.5			
Returns to Surface:	Cement 2 bbls			

Job Notes (fluids pumped / procedures / tools / etc.):

10bbls mudflush, 3bbls fresh, 450sx G (neat) mixed @ 15.8ppg, 0.5bbls displace, top off well

Customer Representative Signature:

Thank You For Using  
O - TEX Pumping

Client	Ensign	Client Rep	Eloy Cossio	Supervisor	Joyner
Ticket No.	1527	Well Name	Wolfum 32-10	Unit No.	445046
Location	SW NE 10:6N:64W	Job Type	Abandonment Plugs	Service District	Brighton
Comments	450sx G (neat) @ 15.8ppg			Job Date	03/13/2017

