

RECEIVED

FEB 26 1971

COLO. OIL & GAS CONS. COMM.

BEST IMAGE
AVAILABLE

HISTORY



COMPANY: General Petroleum Corporation
FIELD: Pagoda Structure

LAND OFFICE: Denver
LEASE NO.: Hale & Miller (Pat'd)
UNIT: Pagoda
I Sec. 598

WELL NO. 33-34-P

LOCATION: 1650' from north line and 1650' from west line of Section 34, located in NW SE NW 34, Township 4 North, Range 89 West, Sixth Principal Meridian, Route County, Colorado.

ELEVATIONS: Rotary Drive Bushings: 7863' - production mat: 7853'. Elevations were established using Well 55-34-G as a datum.

All depth measurements from rotary bushings.

DRILLED BY: Fred M. Manning, Inc., Contractor

SPOUDED: July 14, 1949 FINISHED DRILLING: August 28, 1949

ON PRODUCTION TEST: October 4-8, 1949. Maximum gas rate, 1,960 MCF/D with T.P. of 427' and G.P. of 455#.

PRODUCING HORIZON: Shinarump Sand - 3975' - 4078'.

CASING RECORD: 10-3/4" - 40.50', J-55 cemented at 450' with 300 sacks.
7" - 23', J-55 cemented at 4149' with 300 sacks.
2-7/8" - 6.5', J-55 tubing, bottom at 4045'.

EFFECTIVE PERFORATIONS:	INTERVAL	HOLES
	3975' - 3982'	42 - 9/16" bullets
	3996' - 4007'	66 - 9/16" bullets and 44 - 28-grain cone shots
	4016' - 4030'	84 - 9/16" bullets and 56 - 28-grain cone shots
	4040' - 4048'	48 - 9/16" bullets and 32 - 28-grain cone shots
	4070' - 4078'	48 - 1/2" bullets.

TOTAL DEPTH: 4150'

WELL NO. 33-34-P