

LEGEND:

— = 90° SYMBOL

● = PROPOSED WELLHEAD.

○ = TOP OF GAS & TARGET BOTTOM HOLE.

▲ = SECTION CORNERS LOCATED.

T9S, R94W, 6th P.M.

1984 Alum. Cap,
0.6' High, Mound of
Stones, Fence Corner,
Conduit
Lat: 39.269246°
Long: -107.840699°

2013 Alum. Cap,
#22097, Flush
w/Ground
Lat: 39.269763°
Long: -107.825741°

S86°59'17"W
1496.47' (Meas.)

2007 Alum. Cap,
#22097, 0.3'
Below Ground
Lat: 39.269982°
Long: -107.820465°

N00°02'53"E - 2679.60' (Meas.)

Top of Gas &
Target Bottom Hole
352' FNL 1544' FWL
Lat: 39.268468°
Long: -107.835247°

NICHOLS 0994-24-02W

1792' FNL 2792' FEL
Fin. Pad Elev = 7137.4'
Lat: 39.264672°
Long: -107.830592°

Set Marked Stone,
Fence Corner
Lat: 39.261892°
Long: -107.840699°

N00°01'59"E - 2400.94' (Meas.)

Alum. Cap,
0.2' High, Fence Post,
N-S Fence
Lat: 39.255303°
Long: -107.840698°

2007 Alum. Cap,
#17509, 0.3' High
Lat: 39.255366°
Long: -107.830778°

2010 Alum. Cap,
#22097, 0.4' High
Lat: 39.259045°
Long: -107.820845°

Set Marked Stone,
Mound of Stones,
Steel Post
Lat: 39.255430°
Long: -107.820861°

N02°14'27"E - 2670.22' (Meas.)

N00°14'02"E
1316.87' (Meas.)

N00°13'41"E
1316.98' (Meas.)

S89°34'12"W - 2810.05' (Meas.)

S89°33'24"W - 2809.70' (Meas.)

NOTE DISTANCE TO NEAREST:

BUILDING: N45°E 2153'
BUILDING UNIT: OVER A MILE
HOBUE: OVER A MILE
DOAA: OVER A MILE
PUBLIC ROAD: N03°W 338'
ABOVE GROUND UTILITY: N05°W 374'
RAILROAD: OVER A MILE
PROPERTY LINE: N03°W 461'

NOTE:

- 1.) All latitudes and longitudes are given in NAD 83 coordinates.
- 2.) Distances to nearest section lines are measured perpendicularly.

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE LOCATION HAS BEEN STAKED ON THE GROUND AS SHOWN ON THE PLAT AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 17130
STATE OF COLORADO

08-30-17

PDOP = 1.5

**BASIS OF BEARINGS**

BASIS OF BEARINGS IS A G.P.S. OBSERVATION

BASIS OF ELEVATION

BENCH MARK (19 RDS) LOCATED IN THE SE 1/4 OF SECTION 16, T9S, R93W, 6th P.M., TAKEN FROM THE SOUTH MAMM PEAK, QUADRANGLE, COLORADO, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 7252 FEET.

UELS, LLC

Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

**LARAMIE ENERGY, LLC**

NICHOLS 0994-24-02W
SW 1/4 NE 1/4, SECTION 24, T9S, R94W, 6th P.M.
MESA COUNTY, COLORADO

SURVEYED BY	CODY RICH, B.H.	08-30-16	SCALE
DRAWN BY	S.S.	03-01-17	1" = 1000'

WELL LOCATION PLAT