

## Brady Riley

---

**From:** Diana Burn - DNR <diana.burn@state.co.us>  
**Sent:** Thursday, April 27, 2017 8:11 AM  
**To:** Matthew Schwartz  
**Cc:** Savanna 802; Troy Schindler; Tracey Fallang; Matt Barber; Brady Riley; Steve Jenkins - DNR; Penny Garrison - DNR; Barbara Westerdale - DNR  
**Subject:** RE: Bill Barrett Corporation Unplanned Sidetrack: CVR 5-63-32-4956B2 (05-123-44256)

Please proceed as proposed.

Thanks,  
Diana

---

**From:** Matthew Schwartz [mailto:[maschwartz@billbarrettcorp.com](mailto:maschwartz@billbarrettcorp.com)]  
**Sent:** Wednesday, April 26, 2017 6:51 PM  
**To:** Diana Burn - DNR  
**Cc:** Savanna 802; Troy Schindler; Tracey Fallang; Matt Barber; Brady Riley  
**Subject:** Bill Barrett Corporation Unplanned Sidetrack: CVR 5-63-32-4956B2 (05-123-44256)

Ms. Burn,

As per our conversation, we are required to open hole sidetrack our 6 1/8" lateral hole due to a 28' fish left in the hole from 9553' – 9581' MD (the fish is a 4 3/4" motor and 6 1/8" bit). 9 5/8" surface casing is set at 821' MD, 7" intermediate casing is set at 6744' MD (LP) and the total depth of the wellbore to be abandoned is 9581' MD. We are not proposing to set any cement plugs in the wellbore. Our proposed depth of sidetrack KOP is 8666'MD. The objective formation for the sidetrack hole is the Niobrara formation, which is the same objective formation as the wellbore being abandoned. The PBHL of the sidetrack hole is the same as the wellbore being abandoned (930' FSL, 500' FEL, Section 33 T5N R63W).

Please let me know if you need any more information or if you have any concerns. We will proceed with the submittal of the "Application for Permit to Drill a Sidetrack Wellbore, Form 2" tomorrow as per COGCC guidelines. Thanks, have a good night.

## Matt Schwartz

*Operations Engineer*

Bill Barrett Corporation  
1099 18<sup>th</sup> Street, Suite 2300  
Denver, Colorado 80202

Main: 303.293.9100

Direct Line: 303.312.8142

Fax: 303.291.0420



**Bill Barrett Corporation**