

From: [Burn - DNR, Diana](#)
To: [Matthew Schwartz](#)
Cc: [Troy Schindler](#); [Savanna 802](#); [Brady Riley](#); [Dan Moore](#); [Terry Barrett](#); [Tracey Fallang](#); [Dirk Sutphin](#); [Barbara Westerdale](#); [Garrison, Penny](#)
Subject: Re: Bill Barrett Corporation Unplanned Sidetrack #2: CVR 5-63-32-4956B2 (05-123-44256)
Date: Saturday, April 29, 2017 4:36:29 PM
Attachments: [image002.jpg](#)

Apologize for missing the call.

Please proceed as proposed.

Thanks,
Diana

On Apr 29, 2017 4:12 PM, "Matthew Schwartz" <maschwartz@billbarrettcorp.com> wrote:

Ms. Burn,

As per my voicemail, we are required to perform a second open hole sidetrack our 6 1/8" lateral hole because we are unable to continue drilling the first sidetrack wellbore due to large doglegs and unstable hole encountered soon after a fault at approximately 9500' MD. 9 5/8" surface casing is set at 821' MD, 7" intermediate casing is set at 6744' MD (LP) and the total depth of the wellbore to be abandoned is 9864' MD. We are not proposing to set any cement plugs in the wellbore. Our proposed depth of sidetrack KOP is 8939' MD. The objective formation for the sidetrack hole is the Niobrara formation, which is the same objective formation as the wellbore being abandoned. The PBHL of the sidetrack hole is the same as the wellbore being abandoned (930' FSL, 500' FEL, Section 33 T5N R63W).

For clarity, I have attached a wellbore diagram with the relevant information. Please let me know if you need any more information or if you have any concerns. We will proceed with the submittal of the "Application for Permit to Drill a Sidetrack Wellbore, Form 2" Monday 5/1 as per COGCC guidelines. Thanks, have a good night.

Matt Schwartz

Operations Engineer

Bill Barrett Corporation

1099 18th Street, Suite 2300

Denver, Colorado 80202

Main: [303.293.9100](tel:303.293.9100)

Direct Line: [303.312.8142](tel:303.312.8142)

Fax: [303.291.0420](tel:303.291.0420)

