

FORM  
2  
Rev  
08/16

State of Colorado  
Oil and Gas Conservation Commission  
1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:  
401273600  
**(SUBMITTED)**

APPLICATION FOR PERMIT TO:

Drill       Deepen       Re-enter       Recomplete and Operate

Date Received:

TYPE OF WELL    OIL     GAS     COALBED     OTHER Lateral 1      Refiling   
ZONE TYPE      SINGLE ZONE     MULTIPLE ZONES     COMMINGLE ZONES       Sidetrack

Well Name: Federal 11-90-15      Well Number: 3  
Name of Operator: SG INTERESTS I LTD      COGCC Operator Number: 77330  
Address: 100 WAUGH DR SUITE 400  
City: HOUSTON      State: TX      Zip: 77007  
Contact Name: Tracy Arnett      Phone: (970)3850696      Fax: (970)3850636  
Email: tarnett@sginterests.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: \_\_\_\_\_

WELL LOCATION INFORMATION

QtrQtr: SESW      Sec: 15      Twp: 11s      Rng: 90w      Meridian: 6  
Latitude: 39.094320      Longitude: -107.437850  
Footage at Surface: 575 Feet      FNL/FSL      FSL      1516 Feet      FEL/FWL      FWL  
Field Name: RAGGED MOUNTAIN      Field Number: 71430  
Ground Elevation: 7851      County: GUNNISON  
GPS Data:  
Date of Measurement: 09/17/2013      PDOP Reading: 1.5      Instrument Operator's Name: D. Nicewicz  
If well is  Directional       Horizontal (highly deviated)      **submit deviated drilling plan.**  
Footage at Top of Prod Zone:      FNL/FSL      FEL/FWL      Bottom Hole:      FNL/FSL      FEL/FWL  
688      FSL      1752      FWL      2065      FSL      545      FEL  
Sec: 15      Twp: 11s      Rng: 90w      Sec: 15      Twp: 11s      Rng: 90w

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership:  Fee       State       Federal       Indian  
The Surface Owner is:       is the mineral owner beneath the location.  
(check all that apply)       is committed to an Oil and Gas Lease.  
    has signed the Oil and Gas Lease.  
    is the applicant.  
The Mineral Owner beneath this Oil and Gas Location is:  Fee       State       Federal       Indian  
The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes  
The right to construct the Oil and Gas Location is granted by: oil and gas lease  
Surface damage assurance if no agreement is in place: \_\_\_\_\_      Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

See attached lease map.

Total Acres in Described Lease: 540 Described Mineral Lease is:  Fee  State  Federal  Indian

Federal or State Lease # COC13484

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 600 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet  
Building Unit: 5280 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 1780 Feet  
Above Ground Utility: 5280 Feet  
Railroad: 5280 Feet  
Property Line: 2745 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a:  Buffer Zone  
 Exception Zone  
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 822 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 600 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): Henderson Gulch

Unit Number: COC078411X

## SPACING & FORMATIONS COMMENTS

This well is in the Henderson Gulch Unit.

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CAMEO COAL	CMEOC			

## DRILLING PROGRAM

Proposed Total Measured Depth: 7949 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: \_\_\_\_\_ Feet  No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type:  Annular Preventor  Double Ram  Rotating Head  None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 608

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	40	0	400	180	400	0
1ST	8+1/2	5+1/2	17	0	4664	787	4664	0
1ST LINER	4+3/4	2+7/8	0	0	7949			

Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

### OTHER LOCATION EXCEPTIONS

Check all that apply:

Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_

Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

### OPERATOR COMMENTS AND SUBMITTAL

Comments This is a planned sidetrack from the Federal 11-90-15 #3 well. A Sundry (doc# 401273290) to change the drilling plan for the Federal 11-90-15 #3 is being submitted concurrently with this Form 2. The completed portion of this well will be 600' from the lease line and unit boundary.

This application is in a Comprehensive Drilling Plan       No       CDP #: \_\_\_\_\_

Location ID:       324491      

Is this application being submitted with an Oil and Gas Location Assessment application?       No      

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name:       Tracy Arnett      

Title:       Permitting       Date: \_\_\_\_\_ Email:       tarnett@sginterests.com      

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC \_\_\_\_\_ Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

<b>API NUMBER</b>
05 051 06129 01

### Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>

## Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with open-hole Resistivity Log and Gamma Ray Log from kickoff point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing from kickoff point (or on intermediate casing if production liner is run) into the surface casing or into the overlap between the production and intermediate casing in the event intermediate casing is run. The horizontal portion of a well from kickoff point to TD will be logged-while-drilling with a gamma ray tool. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state 'No open-hole logs were run' and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.

Total: 1 comment(s)

### Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401273616	MINERAL LEASE MAP
401273640	OffsetWellEvaluations Data
401273642	OffsetWellEvaluations Data
401273657	WELL LOCATION PLAT
401273662	DEVIATED DRILLING PLAN
401273679	DIRECTIONAL DATA

Total Attach: 6 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

**Public Comments**

No public comments were received on this application during the comment period.

