

Click here to reset the form

FORM
21
Rev 9/14

State of Colorado
Oil and Gas Conservation Commission



1120 Lincoln Street, Suite 801, Denver, Colorado 80203 (303)-894-2100 Fax: (303)-894-2109

MECHANICAL INTEGRITY TEST

1. Duration of the pressure test must be a minimum of 15 minutes.
2. An original pressure chart must accompany this report if this test was not witnessed by a OGCC representative. Injection wells tests must be witnessed by an OGCC representative.
3. For production wells, test pressures must be a minimum of 300 psig.
4. New injection wells must be tested to maximum requested injection pressure.
5. For injection wells, test pressures must be at least 300 psig or average injection pressure, whichever is greater.
6. A minimum 300 psi differential pressure must be maintained between the tubing and tubing/casing annulus pressure.
7. Do not use this form if submitting under provisions of Rule 326.a.(1) B. or C.
8. OGCC notification must be provided 10 days prior to the test via Form 42.
9. Packers or bridge plugs, etc., must be set within 100 feet of the perforated interval to be considered a valid test.

OGCC Operator Number: 100322	Contact Name and Telephone ERICH ZWAAGSTRA
Name of Operator: NOBLE ENERGY INC	No: (970) 371-7884
Address: 1625 BROADWAY STE 2200	Email: ERICH.ZWAAGSTRA@NBLENERGY.COM
City: DENVER State: CO Zip: 80202	
API Number: 05-123-26373 OGCC Facility ID Number:	
Well/Facility Name: Wells Ranch USX AA Well/Facility Number: 33-25	
Location QtrQtr: NESW Section: 33 Township: 6N Range: 63W Meridian: 6	

FOR OGCC USE ONLY

Document Number:

Date Received:

Complete the
Attachment Checklist

Oper OGCC

Pressure Chart		
Cement Bond Log		
Tracer Survey		
Temperature Survey		
Inspection Number		

☒ SHUT-IN PRODUCTION WELL

☐ INJECTION WELL

Last MIT Date:

Test Type:

☒ Test to Maintain SI/TA status

☐ 5- year UIC

☐ Reset Packer

☐ Verification of Repairs

☐ Annual UIC Test

Describe Repairs or Other Well Activities:

Wellbore Data at Time of Test

Injection/Producing Zone(s) Niobrara/codell	Perforated Interval: 6527-6636/6799-6809	Open Hole Interval:
--	---	---------------------

Casing Test

Use when perforations or open hole is isolated by bridge plug or cement plug; use if cased-hole only with plug back total depth.

Bridge Plug or Cement Plug Depth
6477

Tubing Casing/Annulus Test

Tubing Size: 2 3/8	Tubing Depth: 5962	Top Packer Depth:	Multiple Packers? <input type="checkbox"/> Yes <input type="checkbox"/> No
-----------------------	-----------------------	-------------------	---

Test Data

Test Date 5/4/17	Well Status During Test Shut in	Casing Pressure Before Test 474 476	Initial Tubing Pressure 0	Final Tubing Pressure
Casing Pressure Start Test 962	Casing Pressure - 5 Min. 960	Casing Pressure - 10 Min. 960	Casing Pressure Final Test 959	Pressure Loss or Gain During Test 3 PSI
Test Witnessed by State Representative? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		OGCC Field Representative (Print Name):		

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct, and complete.

Print Name: Zwagstra Erich

Signed: [Signature] Title: Senior Completions Foreman Date: 5/4/17

OGCC Approval: Title: Date:

Conditions of Approval, if any: