



Partner Summary Report - Costs Included

Date: 3/21/2017

Report #: 1

Well Name: CHRISTIANSEN 35-42

DOL:

Spud Date: 10/9/2000

Well Name CHRISTIANSEN 35-42	Operator NOBLE ENERGY, INC.	API 05-123-20071	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB)	Current PBTD (mKB) ORIGINAL HOLE - 7,118.0
---------------------------------	-----------------------------------	---------------------	-----------------------	----------------------------	------------------------------	--

Spud Date 10/9/2000	TD Date 10/13/2000	Rig Release Date 10/14/2000	First Production Date 10/23/2000
------------------------	-----------------------	--------------------------------	-------------------------------------

Rig Name LEED ENERGY SERVICES CORP.	Rig Number 714
--	-------------------

Prospect Number	Prospect	Actual Latitude (°) 40.44192000	Actual Longitude (°) -104.85782800	Quarter 3 NW	Quarter 4 SE	Section 35	Township 6	Twntshp N/S Dir N	Range E/W Dir W
-----------------	----------	------------------------------------	---------------------------------------	-----------------	-----------------	---------------	---------------	----------------------	--------------------

--

Report Start Date 3/21/2017 06:00	Report End Date 3/21/2017 18:00	Operations Summary SFTY MTG-CHECK WHSIP(550/600 SRF 0)-BLEED WELL-T/TANK-RC 90 BBLS TO CONTROL FLOW- PERFORM BI-ANNUAL RIG INSPECTION-ND TREE-NU BOP'S-UNLND TBG-TALLY OOH W/80 JTS OF 2 3/8" 4.7# 8RD EUE J-55 PROD TBG (2586')-LD 138 JTS ON TRAILER-RU CHS WL-RIH W/CIBP- CORRELATE CCL-SET CIBP @ 6990'-POOH-RIH W/DUMP BAILER-SPOT 2 SKS OF CEMENT ON CIBP- POOH-RD WL-MU NC-TIH W/80 JTS OF 2 3/8"OOD-LD 2 JTS-SI-DRAIN UP-SECURE LOC
--------------------------------------	------------------------------------	--

--

--