

**FORM
INSP**

Rev
X/15

**State of Colorado
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:

05/11/2017

Submitted Date:

05/15/2017

Document Number:

675103590

FIELD INSPECTION FORM

Loc ID 335678 Inspector Name: GRANAHAN, KYLE On-Site Inspection 2A Doc Num: _____

Status Summary:

- THIS IS A FOLLOW UP INSPECTION
- FOLLOW UP INSPECTION REQUIRED
- NO FOLLOW UP INSPECTION REQUIRED

Operator Information:

OGCC Operator Number: 10447
Name of Operator: URSA OPERATING COMPANY LLC
Address: 1050 17TH STREET #1700
City: DENVER State: CO Zip: 80265

Findings:

- 7 Number of Comments
- 0 Number of Corrective Actions
- Corrective Action Response Requested

Contact Information:

Contact Name	Phone	Email	Comment
Knudson, Dwayne	(970) 456-3335	dknudson@ursaresources.com	All Inspections
Lind, Jennifer	(720) 508-8362	jlind@ursaresources.com	All Inspections

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
449838	WELL	DG	05/06/2017		103-12283	BR C-240 32D-24-2-98	DG

General Comment:

[On location to witness surface cement job, form 42 doc # 401278224](#)

Location

Overall Good:

Signs/Marker:

Type	DRILLING/RECOMP		
Comment:	Complete/present		
Corrective Action:		Date:	

Emergency Contact Number:

Comment:

Corrective Action: Date: _____

Overall Good:

Spills:

Type	Area	Volume		

In Containment: No

Comment:

Multiple Spills and Releases?

Venting:

Yes/No	NO		
Comment:			
Corrective Action:		Date:	

Flaring:

Type		
Comment:		
Corrective Action:		Date:

Inspected Facilities

Facility ID: 449838 Type: WELL API Number: 103-12283 Status: DG Insp. Status: DG

Cement

Cement Contractor

Contractor Name: Halliburton

Contractor Phone: GJ office

Surface Casing

Cement Volume (sx): 1435

Circulate to Surface: NO

Cement Fall Back: YES

Top Job, 1" Volume: YES

Intermediate Casing

Cement Volume (sxs): _____

Good Return During Job: _____

Production Casing

Cement Volume (sx): _____

Good Return During Job: _____

Plugging Operations

Depth Plugs(feet range): _____

Cement Volume (sx): _____

Good Return During Job: _____

Cement Type: _____

Comment:

TD - 3800'
 Casing TD - 3777'
 DV stage tool - 1658'
 Last centralizer ran at - 61'
 Stage 1 -
 20 bbls h20 spacer
 291 bbls 12.5 ppg cement
 displace with 289 bbls mud
 Lost circulation at 190-200bbls into to displacement - 480-500 psi lift pressure at 8bbls per min
 Land plug/check floats - held/drop dv opening tool/ open tool with halliburton truck pump/establish circulation/circulate from dv tool to surface for 4 hrs/pumped bottoms up volume - no cement to surface
 Cement blend -
 12.5 ppg
 1.94 yield
 10.15 gals h20/sk

 Stage 2 -
 20 bbls h20 spacer
 258 bbls 12.3ppg cement
 displace 128 bbls with h20
 cement to surface at 17 bbls into displacement
 111 bbls cement to surface
 land plug/release pressure/ ensure plug holds - plug held/ rig down
 Check for cement fall back - Cement has fallen - unable to determine top of cement at time of inspection.
 Cement blend -
 12.3 ppg
 2.45 yield
 14.18 gals h20/sk

Corrective Action: _____

Date: _____

Reclamation - Storm Water - Pit

Storm Water:

Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment
				Covering Materials	Pass	
Compaction	Pass					
				Material Handling And Spill Prevention	Pass	
Berms	Pass					
Sediment Traps	Pass					
Retention Ponds	Pass					

Comment:

Corrective Action:

Date: _____

Pits: NO SURFACE INDICATION OF PIT

Attached Documents

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
401284149	INSPECTION SUBMITTED	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4147836