



Partner Summary Report - Costs Included

Date: 3/22/2017

Report #: 1

Well Name: RAY-GLO 01

DOL:

Spud Date: 3/4/1986

Report Start Date
3/22/2017 06:00

Report End Date
3/22/2017 13:00

Operations Summary

CHECK PRESSURES ON WELL 50 ON PRODUCTION CASING, 450 ON TUBING AND 0 PSI ON SURFACE. VERIFY SHUT IN STATUS ON WELL. NOT IN THE CONSENT DECREE AREA. LEASE OPERATOR OPENED WELL TO PRODUCTION FACILITY. TUBING BLEW DEAD. HOLD PRE JOB SAFETY MEETING, RIG UP CASED HOLE SOLUTIONS AND BREAK DOWN WELL HEAD. MASTER VALVE LEAKING BY SLIGHTLY. STACK NEW MASTER VALVE ON. RIH WITH 1.75 GAUGE RING TO SEATING NIPPLE AT 6812'. POOH PICK UP 2 3/8 OWEN CIBP AND RIH AND SET AT 6796', 16' ABOVE SEATING NIPPLE. CONFIRM SET BY STACKING OUT ON PLUG. POOH WITH SETTING TOOLS AND BLOW TUBING DEAD. RIG DOWN CASED HOLE SOLUTIONS. CHANGE OUT MASTER VALE TO 5K MASTER VALVE. REPLACE SIDE VALVES WITH 5K BALONS AND NEW NIPPLES. SHUT WELL IN