



Partner Summary Report

Date: 3/29/2017

Report #: 2

Well Name: STATE M36-07

DOL:

Spud Date: 11/27/2005

Well Header

Well Name STATE M36-07	API 05-123-23206	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB)	Current PBTD (mKB) ORIGINAL HOLE - 7,416.0
---------------------------	---------------------	-----------------------	----------------------------	------------------------------	-----------------------------------------------

Report Start Date
3/29/2017 10:00

Report End Date
3/29/2017 18:30

Operations Summary

HOLD SAFETY MEETING. MOVE RIG FROM THE STATE 05-36 TO LOCATION. SPOT UNIT AND EQUIPMENT. RIG UP FOR WORK OVER OPERATIONS.

IWP =
TBG = 700 PSI,
CSG = 700 PSI,
SURFCSG = 80 PSI.

UNSECURED AND BLOW WELL DOWN. R/U CIRC EQUIPMENT, LOAD/PUMP 110 BBLS 2 BPM @ 200 PSI TO CLEAN WELL. N/D PRODUCTION TREE AND N/U BOPE, FUNCTION TEST. TOOH W/ 72 JNTS TO DERRICK, LAY DOWN 140 JNTS TO FLOAT. HOLD SAFETY MEETING WITH CASED HOLE, MIRU, M/U 4 -1/2 CIBP AND RIH T/ 6,971' AND SET. M/U DUMP BAILER AND RIH TO CIBP @ 6,971' DUMP BAIL 2 SXS. RDMO. LOAD HOLE W/ 84 BBLS FRESH WATER. SECURE WELL AND LOCATION. SDFN