

Document Number:
401262732

Date Received:
04/19/2017

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 69175 Contact Name: Kelsi Welch

Name of Operator: PDC ENERGY INC Phone: (303) 831-3974

Address: 1775 SHERMAN STREET - STE 3000 Fax: _____

City: DENVER State: CO Zip: 80203 Email: kelsi.welch@pdce.com

For "Intent" 24 hour notice required, Name: Gomez, Jason Tel: (970) 573-1277

COGCC contact: Email: jason.gomez@state.co.us

API Number 05-123-20486-00

Well Name: NOFFSINGER Well Number: 32-5

Location: QtrQtr: SWNE Section: 5 Township: 5N Range: 64W Meridian: 6

County: WELD Federal, Indian or State Lease Number: _____

Field Name: WATTENBERG Field Number: 90750

Notice of Intent to Abandon Subsequent Report of Abandonment

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.429470 Longitude: -104.571690

GPS Data:
Date of Measurement: 06/03/2010 PDOP Reading: 2.0 GPS Instrument Operator's Name: Holly L. Tracy

Reason for Abandonment: Dry Production Sub-economic Mechanical Problems

Other _____

Casing to be pulled: Yes No Estimated Depth: 575

Fish in Hole: Yes No If yes, explain details below

Wellbore has Uncemented Casing leaks: Yes No If yes, explain details below

Details: _____

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
CODELL	6866	6876			

Total: 1 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	12+1/4	8+5/8	24	356	265	356	0	VISU
1ST	7+7/8	4+1/2	10.5	7,058	150	7,058	6,040	CBL
S.C. 1.1				7,058	270	6,040	3,700	CBL

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 6816 with 2 sacks cmt on top. CIBP #2: Depth 6476 with 2 sacks cmt on top.
 CIBP #3: Depth _____ with _____ sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
 CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 240 sks cmt from 625 ft. to 0 ft. Plug Type: STUB PLUG Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
(Cast Iron Cement Retainer Depth)
 Set _____ sacks half in. half out surface casing from _____ ft. to _____ ft. Plug Tagged:
 Set _____ sacks at surface
 Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: Yes No
 Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: _____ ft. _____ inch casing Plugging Date: _____
 of _____
 *Wireline Contractor: _____ *Cementing Contractor: _____
 Type of Cement and Additives Used: _____
 Flowline/Pipeline has been abandoned per Rule 1103 Yes No *ATTACH JOB SUMMARY

Technical Detail/Comments:

Noffsinger 32-5 (05-123-20486)/Plugging Procedure (Intent)
 Producing Formation: Codell 6866'-6876'
 TD: 7075' PBDT: 7017'
 Existing Retrievable Bridge Plug at: 6791' with 2 sxs sand.
 Surface Casing: 8 5/8" 24# @ 356' w/265 sxs.
 Production Casing: 4 1/2" 10.5 & 11.6# @ 7058' w/ 420 sks cmt. (TOC at 3680' - CBL.)

Tubing: 2 3/8" tubing set at 6470'. (11/21/2016)

Proposed Procedure:

1. MIRU RU pulling unit. PU tubing. Clean out well to retrievable bridge plug at 6791'. Pull retrievable bridge plug and TOO H with tubing and RBP.
2. RU wireline company.
3. TIH with CIBP. Set BP at 6816'. Top with 2 sxs 15.8#/gal CI G cement.
4. TIH with CIBP. Set BP at 6476'. Top with 2 sxs 15.8#/gal CI G cement.
5. TIH with casing cutter. Cut off 4 1/2" casing at 575'. Pull cut casing.
6. TIH with tubing to 625'. Mix and pump 240 sxs 15.8#/gal CI G cement down tubing. Cement should circulate to surface.
7. Cut surface casing 6' below ground level and weld on cap.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kelsi Welch
 Title: Production Tech Date: 4/19/2017 Email: kelsi.welch@pdce.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved by _____
NOFFSINGER, STEVE

COGCC Approved: _____

Date: 6/1/2017

CONDITIONS OF APPROVAL, IF ANY: _____

Expiration Date: 11/30/2017

COA Type

Description

	1) Provide 48 hour notice of plugging MIRU via electronic Form 42. 2) For the 625' plug: pump plug and displace. If surface casing plug is not circulated to surface then tag plug – must be at 215' or shallower and provide 10 sx plug at the surface. Leave at least 100' of cement in the casing for each plug. 3) Properly abandon flowlines as per Rule 1103. File electronic Form 42 once abandonment complete. 4) Prior to starting plugging operations a Bradenhead test shall be performed. If the beginning pressure is greater than 25 psi, or if pressure remains at the conclusion of the test, or if any liquids were present contact COGCC Engineering for sampling requirements. The Form 17 shall be submitted within 10 days of the test.
--	---

Attachment Check List

Att Doc Num

Name

401262732	FORM 6 INTENT SUBMITTED
401262857	WELLBORE DIAGRAM
401262858	WELLBORE DIAGRAM

Total Attach: 3 Files

General Comments

User Group

Comment

Comment Date

Public Room	Document verification complete 04/25/17	04/25/2017
Permit	Passes permitting. The Form 5A#401210415 erroneously reported 2 sks of cement(sand plug) on top of the RBP set @ 6,791'-6,798'.	04/20/2017

Total: 2 comment(s)