

US ROCKIES REGION  
Operation Summary Report

Well: SARCHET 15-33A				Spud date: 7/19/2002					
Project: COLORADO-WELD-NAD83-UTM13				Site: SARCHET 15-33A				Rig name no.: CONCORD 4/4	
Event: ABANDONMENT				Start date: 4/27/2017			End date: 5/11/2017		
Active datum: RKB @4,879.99usft (above Mean Sea Level)				UWI: 0/3/N/67/W/33/0/SESW/6/0/0/0/0/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation	
12/14/2016	11:00 - 12:00	1.00	ABANDP	53	B	P		FORM 17 TEST	
4/24/2017	-								
4/27/2017	9:00 - 10:00	1.00	ABANDP	30	G	P		MI CONCORD 4, SPOT IN EQUIPMENT, PUMP, TANK, BASE BEAM, WO RIG	
	10:00 - 11:00	1.00	ABANDP	30	A	P		LD PUMP LIONES, RU WO RIG, CHECK WELL PRESSURES, 300/ 300/0#	
	11:00 - 12:00	1.00	ABANDP	30	E	P		BLOW DOWN WELL TO WORK TANK, START PUMP AND KILL WELL W/ 45BBLs OF C2O/BIO	
	12:00 - 12:30	0.50	ABANDP	30	F	P		ND WH, NU BOPS/WF, ULAND 2 3/8 TBG, GET EQUIPMENT READY TO TOO, H,	
	12:30 - 14:00	1.50	ABANDP	31	I	P		TOOH W/ 2 3/8 TBG SB, AND TALLY,	
	14:00 - 14:30	0.50	ABANDP	34	I	P		MIRU WL, HELD JSA MEETING, RU TOOLS,	
	14:30 - 15:30	1.00	ABANDP	34	O	P		PU GAUGE RING RIH DOWN TO 7730', POOH,	
	15:30 - 17:30	2.00	ABANDP	34	I	P		PU 4.5 CIBP,RIH & SET PLUG @ 7720', PU 2SX OF CMT AND DUMP AIL ON TOP OF CIBP @ 7720', POOH, PU 2ND 4.5 CIBP, RIH & SET @ 7100', POOH, RDMO WL	
	17:30 - 19:30	2.00	ABANDP	31	I	P		TIH W/ TBG,M TAG CIBP @ 7100', CLOSE ELL SDFN,	
	19:30 - 20:30	1.00	ABANDP	30	G	P		CT TO YARD	
4/28/2017	6:00 - 7:00	1.00	ABANDP	30	G	P		CT TO LOC, HELD JSA MEETING, REFER TO SAFETY TAB, OPEN WELL,	
	7:00 - 8:00	1.00	ABANDP	31	H	P		RU PUMP LINES, ROLL HOLE TO GET ALL GAS OUT, PRESSURE TEST CSG TO 1000# HELD FOR 15MIN, TEST GOOD, RELEASE PRESS,	
	8:00 - 8:30	0.50	ABANDP	51	E	P		MIRU SLB, HELD JSA MEETING, RU CMT LINE	
	8:30 - 9:30	1.00	ABANDP	51	D	P		PUMP NIO BALANCE PLUG, 40SX @ 15.8PPG, 1.53 YIELD, 10.9 BBLs OF CMT, RDMO SLB	
	9:30 - 11:30	2.00	ABANDP	31	I	P		TOOH, SB 1100' OF TBG ON DERRICK AND LD THE REST ON TRAILER	
	11:30 - 12:30	1.00	ABANDP	34	I	P		MIRU WL,HELD JSA MEETING, PU 4.5 CIBP AND SET @ 4010', 200FT AVOBE SUSX PERF, DUMP 2SX OF CMT ON TOP OF CIBP, POOH	
	12:30 - 13:30	1.00	ABANDP	34	L	P		PU & RIH W/ JET CUT, CUT CSG @ 1000', POOH RDMO WL,	
	13:30 - 15:00	1.50	ABANDP	31	I	P		ND BOPS, UNLAND 4.5 CSG, LD 24JNTS ON TRAILER, CHANGE OVER TOOLS, TO TIH w 2 3/8 TBG,	
	15:00 - 15:30	0.50	ABANDP	31	I	P		TIH W 2 3/8 TBG LAND EOT @ 1100',	
	15:30 - 16:00	0.50	ABANDP	31	H	P		RU PUMP LINES, ROLL HOLE	
	16:00 - 17:30	1.50	ABANDP	51	D	P		MIRU SLB, PRESSURE TEST LINE TO 2K, PUMP STUB PLUG 232SX @ 15.8PPG, 1.5 YIELD, 70BBLs OF CMT, RDMO SLB,	
	17:30 - 18:00	0.50	ABANDP	31	H	P		PUH TO 105', AND REVERSE CIRC TO ENSURE NO CMT IS LEFT ON TBG OR CSG	
	18:00 - 18:30	0.50	ABANDP	31	I	P		TOOH, CLOSE WELL,	
	18:30 - 19:30	1.00	ABANDP	30	G	P		CT TO YARD,	
5/1/2017	6:00 - 7:00	1.00	ABANDP	30	G	P		CT TO LOC, HELD JSA MEETING, REFER TO SAFETY TAB, OPEN WELL,	

US ROCKIES REGION  
Operation Summary Report

Well: SARCHET 15-33A

Spud date: 7/19/2002

Project: COLORADO-WELD-NAD83-UTM13

Site: SARCHET 15-33A

Rig name no.: CONCORD 4/4

Event: ABANDONMENT

Start date: 4/27/2017

End date: 5/11/2017

Active datum: RKB @4,879.99usft (above Mean Sea Level)

UWI: 0/3/N/67/W/33/0/SESW/6/0/0/0/0/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	7:00 - 8:00	1.00	ABANDP	34	1	P		MIRU WL, HELD JSA MEETING, PU WEIGHT BAR, RIH & TAG TOC @ 119', POOH,
	8:00 - 8:30	0.50	ABANDP	34	I	P		PU 8.625 CIBP, TIH & SET PLUG @ 80', POOH RDMO WL,
	8:30 - 9:30	1.00	ABANDP	30	C	P		PU LOC, RDMO CONCORD 4, SPOT IN WINCH TRUCK AND LOAD EQUIPMENT,
5/11/2017	6:00 - 7:00	1.00	ABANDP	52		P		pressure tested CIBP, surface casing to 500 psi
	7:00 - 8:00	1.00	ABANDP	53	B	P		dug up surface casing
	8:00 - 9:00	1.00	ABANDP	53	C	P		cut casing 6' below GL, tagged @ 71'
	9:00 - 10:00	1.00	ABANDP	53	B	P		filled casing stub with 33 bags 5000 psi cement
	10:00 - 11:00	1.00	ABANDP	53	A	P		capped casing with a metal plate containing well info
	11:00 - 12:00	1.00	ABANDP	53	B	P		backfilled
	10:00 - 10:00	0.00	ABANDP	50		P		P&A'd OFFLINE. JSND.