

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

401280731

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10459

Contact Name: Kamrin Ruder

Name of Operator: EXTRACTION OIL &amp; GAS LLC

Phone: (720) 9747743

Address: 370 17TH STREET SUITE 5300

Fax:

City: DENVER

State: CO

Zip: 80202

API Number 05-123-42557-00

County: WELD

Well Name: Stromberger

Well Number: 8

Location: QtrQtr: SENE Section: 22 Township: 6N Range: 67W Meridian: 6

Footage at surface: Distance: 2058 feet Direction: FNL Distance: 150 feet Direction: FEL

As Drilled Latitude: 40.474059 As Drilled Longitude: -104.870861

## GPS Data:

Date of Measurement: 04/26/2017 PDOP Reading: 2.0 GPS Instrument Operator's Name: Ryan Desmond

\*\* If directional footage at Top of Prod. Zone Dist.: 2408 feet. Direction: FNL Dist.: 460 feet. Direction: FWL

Sec: 23 Twp: 6N Rng: 67W

\*\* If directional footage at Bottom Hole Dist.: 2450 feet. Direction: FNL Dist.: 524 feet. Direction: FEL

Sec: 24 Twp: 6N Rng: 67W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 02/22/2017 Date TD: 04/09/2017 Date Casing Set or D&amp;A: 04/09/2017

Rig Release Date: 04/10/2017 Per Rule 308A.b.

## Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 16782 TVD\*\* 6868 Plug Back Total Depth MD 16769 TVD\*\* 6868

Elevations GR 4778 KB 4803 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

## List Electric Logs Run:

CBL, MUD, MWD, (Triple Combo in API 123-42559)

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	42	0	80	100	0	80	VISU
SURF	12+1/4	9+5/8	36	0	1,556	550	0	1,556	VISU
1ST	7+7/8	5+1/2	20	0	16,769	2,750	90	16,769	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,535		NO	NO	
SUSSEX	4,061		NO	NO	
SHANNON	4,612		NO	NO	
SHARON SPRINGS	6,950		NO	NO	
NIOBRARA	7,042				

Comment:

The TPZ footages are estimates calculated through Directional Plotting Software—from where the production string (5 ½" casing) crosses the 460' setback hardline.  
The triple combo log was ran on Stromberger 2 (123-42559).

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Kamrin Ruder

Title: Drilling Technician Date: \_\_\_\_\_ Email: kruder@extractionog.com

### Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
401297393	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
401297396	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
401297374	PDF-GAMMA RAY	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401297376	LAS-GAMMA RAY	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401297377	PDF-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401297383	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401297398	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)