



## Partner Summary Report

Date: 4/7/2017

Report #: 2

Well Name: STARMAN USX A17-16

DOL:

Spud Date: 12/7/2008

### Well Header

Well Name STARMAN USX A17-16	API 05-123-29570	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB)	Current PBTD (mKB) ORIGINAL HOLE - 7,155.7		
Spud Date 12/7/2008	TD Date 12/10/2008	Rig Release Date 12/12/2008	First Gas Sales				
Actual Latitude (°) 40.48002158	Actual Longitude (°) -104.56630508	Quarter 3 SE	Quarter 4 SE	Section 17	Township 6	Township N/S Dir N	Range E/W Dir W

Report Start Date 4/7/2017 06:00	Report End Date 4/7/2017 17:30	Operations Summary WHP - TBG 1100, CSG 1700, SURF CSG 0. RIG UP PUMP AND TANK. BLOW DOWN WELL. TOOK 2 HOURS. CIRCULATE. TOOK 1.5 HOURS TO KILL WELL. ND WELLHEAD. NU BOP. POOH W/ TBG. SB 4500' LD REMAINDER. RIG UP WL. RIH W/ CIBP AND SET AT 6679'. POOH W/ WL. RIH W/ DB. DB 2 SX CMT ON CIBP. LOAD WELL. PRESSURE TEST CIBP TO 1000 PSI FOR 15 MINUTES. NO LEAK OFF. SECURE WELL. SWIFN.
-------------------------------------	-----------------------------------	--