

FORM  
INSPRev  
X/15

## State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:

06/01/2017

Submitted Date:

06/12/2017

Document Number:

666803216

### FIELD INSPECTION FORM

Loc ID 322296 Inspector Name: Murray, Richard On-Site Inspection  2A Doc Num: \_\_\_\_\_

**Operator Information:**

OGCC Operator Number: 10043  
Name of Operator: MACKLEY\* ARNOLD & DARLEEN  
Address: 4031 COUNTY RD 320  
City: RIFLE State: CO Zip: 81650

**Status Summary:**

- THIS IS A FOLLOW UP INSPECTION  
 FOLLOW UP INSPECTION REQUIRED  
 NO FOLLOW UP INSPECTION REQUIRED

**Findings:**

2 Number of Comments  
0 Number of Corrective Actions  
 Corrective Action Response Requested

**Contact Information:**

Contact Name	Phone	Email	Comment
Murray, Richard	970-623-9782	G.Richard.Murray@state.co.us	

**Inspected Facilities:**

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
210181	WELL	DM	02/24/1961	GW	045-05076	ED T. BERNKLAU 1	DM

**General Comment:**

[Bernklau P&A project](#)

**Inspected Facilities**

Facility ID: 210181 Type: WELL API Number: 045-05076 Status: DM Insp. Status: DM

**Workover**

Comment: MI flare stack, MI and RU MWS Rig #3, RU Service Unit, SICP 45 psi, SITP 630 psi, Braden head 0 psi. RU flow line to Flare stack, Vent tbg to stack and burn off Gas for approx. ½ hr. RU line to tbg annulus and Vent and burn of gas for approximately ¾ hr. ND Well head and prep to kill well. RU pump to annulus and pumped 20 bbls water, well on a vacuum. Pumped 8 bbls water into tbg, Tbg on a vacuum. Nipple down tree, Stripped on BOP and NU same. Secured well and sdfn.

Corrective Action:

Date: