

**FORM
INSP**Rev
X/15**State of Colorado
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

06/02/2017

Submitted Date:

06/12/2017

Document Number:

666803218**FIELD INSPECTION FORM**

Loc ID 322296 Inspector Name: Murray, Richard On-Site Inspection ☐ 2A Doc Num: _____

Operator Information:OGCC Operator Number: 10043Name of Operator: MACKLEY* ARNOLD & DARLEENAddress: 4031 COUNTY RD 320City: RIFLE State: CO Zip: 81650**Status Summary:**

- ☐ THIS IS A FOLLOW UP INSPECTION
☐ FOLLOW UP INSPECTION REQUIRED
☒ NO FOLLOW UP INSPECTION REQUIRED

Findings:1 Number of Comments0 Number of Corrective Actions☐ Corrective Action Response Requested**Contact Information:**

Contact Name	Phone	Email	Comment
Murray, Richard	970-623-9782	G.Richard.Murray@state.co.us	

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
210181	WELL	DM	02/24/1961	GW	045-05076	ED T. BERNKLAU 1	DM

General Comment:

Inspected Facilities									
Facility ID:	210181	Type:	WELL	API Number:	045-05076	Status:	DM	Insp. Status:	DM
Workover									
Comment:	June 2, 2017 Friday Tbg on a vacuum. Casing static. POOH with tbg, RU RMWS to pull CBL Tagged fluid in well at 440' RIH and tagged with tools at 3952' Pulled CBL from tag to surface. RIH with tbg to 3627' Mixed and spotted 22 sks Class G cement with 50# of cacI2 added to slurry. POOH with 30 joints. Waited 2.5 hrs on Cement to set. RIH with tbg, tagged at 3353'. POOH with tbg. PU and RIH with a 4-1/2"								
Corrective Action:								Date:	