

Inspected Facilities

Facility ID: 210181 Type: WELL API Number: 045-05076 Status: DM Insp. Status: PA

Cement

Cement Contractor

Contractor Name: _____ Contractor Phone: _____

Surface Casing

Cement Volume (sx): _____ Circulate to Surface: _____
 Cement Fall Back: _____ Top Job, 1" Volume: _____

Intermediate Casing

Cement Volume (sxs): _____ Good Return During Job: _____

Production Casing

Cement Volume (sx): _____ Good Return During Job: _____

Plugging Operations

Depth Plugs(feet range): 618 Cement Volume (sx): 55

Good Return During Job: _____ Cement Type: Class G

Comment: PU 2 jts and land at 55', Mixed and pumped 15 sks Class G cement and displaced with 1/2 bbl water.

Corrective Action: _____ Date: _____

Workover

Comment: June 7, 2017, Wednesday
 PU a 6-1/8" junk mill, Drill Collars, XO's and tbg. Tagged and RU to drill. Circulated with the well bore fluid, light mud. Drilled on Retainer from 8:30 am to 12:00 noon, retainer went down hole. RIH and tagged up at 555'. POOH with tbg, laid down drill collars and mill. RIH with opened ended 2-3/8" tbg and tagged at 618'. RU to mix cement, mixed and pumped 55 sks class G and displaced with 1.5 bbls water. POOH and laid down tbg. PU 2 jts and land at 55', Mixed and pumped 15 sks Class G cement and displaced with 1/2 bbl water. Laid down 2 jts tbg. Found cement about 2' from top of 7" casing. RD MWS Rig #3. Cleaned up location, racked up equipment. Emptied flat tank, fluid to haul to disposal, will clean tank at Blac-Frac yard and load on disposal load. Dug a cellar around the well head, very hard and full of rocks. Cut off 7" casing at 42" from Ground level and welded on a Dry hole plate, Back filled cellar and moved equipment off of location.

Corrective Action: _____ Date: _____

Attached Documents

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
666803223	Bernklau 1	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4168572
666803224	Bernklau 1-2	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4168573