

**FORM
INSP**

Rev
X/15

**State of Colorado
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:

05/31/2017

Submitted Date:

06/08/2017

Document Number:

670201495

FIELD INSPECTION FORM

Loc ID 450650 Inspector Name: BURGER, CRAIG On-Site Inspection 2A Doc Num: _____

Status Summary:

- THIS IS A FOLLOW UP INSPECTION
- FOLLOW UP INSPECTION REQUIRED
- NO FOLLOW UP INSPECTION REQUIRED

Operator Information:

OGCC Operator Number: 99999
Name of Operator: OLD OPERATORS - STATUS UNKNOWN
Address: SEE COMMENT LINE IN WELL
City: XXXXXXX State: XX Zip: _____

Findings:

- 2 Number of Comments
- 1 Number of Corrective Actions
- Corrective Action Response Requested

Contact Information:

Contact Name	Phone	Email	Comment
Andrews, Dave		david.andrews@state.co.us	

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
450647	WELL	TA	05/17/2017	GW	077-10381	DB Orphan 8	TA

General Comment:

Orphan well plugging project #PO PHAA 2017*12735. Contractor is RACS LLC.

Inspected Facilities

Facility ID: 450647 Type: WELL API Number: 077-10381 Status: TA Insp. Status: TA

Workover

Comment: On location 7am. RACS setting up for circulation and picking up power swivel. 10:30 picking up washover pipe to begin washing over fish. 11:55 began washing over. At 12' water began coming around cellar. Cleaned up. Lassoed fish with whipstock and pulled with 5000 lbs. No movement of fish. Began rigging up to cement. Dave Andrews on location 5-8pm. Mix and pump 30 sacks Class G down casing to heal around cellar (15.8 ppg) at 6pm. Wash out and shut down for night with casing shut in. Dave Andrews returned at 10:30pm and opened valve, some pressure and blew down in about 1 minute. No fluid.

Corrective Action: **Plug and abandon.**

Date: 06/09/2017