

**FORM
INSP**Rev
X/15

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:

06/06/2017

Submitted Date:

06/08/2017

Document Number:

670201499**FIELD INSPECTION FORM**

Loc ID 450650 Inspector Name: BURGER, CRAIG On-Site Inspection ☐ 2A Doc Num: _____

Operator Information:OGCC Operator Number: 99999Name of Operator: OLD OPERATORS - STATUS UNKNOWNAddress: SEE COMMENT LINE IN WELLCity: XXXXXXX State: XX Zip: _____**Status Summary:**

- ☒ THIS IS A FOLLOW UP INSPECTION
☒ FOLLOW UP INSPECTION REQUIRED
☐ NO FOLLOW UP INSPECTION REQUIRED

Findings:2 Number of Comments1 Number of Corrective Actions☒ Corrective Action Response Requested**Contact Information:**

Contact Name	Phone	Email	Comment
Andrews, Dave		david.andrews@state.co.us	

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
450647	WELL	TA	05/17/2017	GW	077-10381	DB Orphan 8	TA

General Comment:

[Orphan well plugging project #PO PHAA 2017*12735. Contractor is RACS LLC.](#)

Inspected FacilitiesFacility ID: 450647 Type: WELL API Number: 077-10381 Status: TA Insp. Status: TA**Workover**

Comment: 7:30. Ran camera to 35'. No visibility due to gas bubbles. 8:30 ran impression block. Stacked out and got no impression. Rigged up to wash down and retry. 9:00 washing down with washover pipe. 10:00 ran impression block. Looks like no more fish in hole. Measured flow out of 2" with garbage bag about 40 gal in 20 min. 12:45 reaming out with 6 3/4" drill bit. Shut down 13:30 to 14:00 due to power swivel issue. 14:45 remaining at 33'. 15:45 drilling formation at 60', slight rate increase. 17:00 drilled to TD from ground surface of 90.9'. 17:30 off location.

Corrective Action: **Plug and abandon.**

Date: 06/09/2017