

**FORM
INSP**Rev
X/15

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:

06/07/2017

Submitted Date:

06/08/2017

Document Number:

670201500**FIELD INSPECTION FORM**

Loc ID 450650 Inspector Name: BURGER, CRAIG On-Site Inspection ☐ 2A Doc Num: _____

Operator Information:OGCC Operator Number: 99999Name of Operator: OLD OPERATORS - STATUS UNKNOWNAddress: SEE COMMENT LINE IN WELLCity: XXXXXXX State: XX Zip: _____**Status Summary:**

- ☒ THIS IS A FOLLOW UP INSPECTION
☒ FOLLOW UP INSPECTION REQUIRED
☐ NO FOLLOW UP INSPECTION REQUIRED

Findings:2 Number of Comments1 Number of Corrective Actions☒ Corrective Action Response Requested**Contact Information:**

| Contact Name | Phone | Email | Comment |
|---------------|-------|---------------------------|---------|
| Andrews, Dave | | david.andrews@state.co.us | |

Inspected Facilities:

| Facility ID | Type | Status | Status Date | Well Class | API Num | Facility Name | Insp Status |
|-------------|------|--------|-------------|------------|-----------|---------------|-------------|
| 450647 | WELL | TA | 05/17/2017 | GW | 077-10381 | DB Orphan 8 | TA |

General Comment:

Orphan well plugging project #PO PHAA 2017*12735. Contractor is RACS LLC.

Inspected FacilitiesFacility ID: 450647 Type: WELL API Number: 077-10381 Status: TA Insp. Status: TA**Workover**

Comment: Shut in well with gauge. Built to 10 psi after 45 minutes. Ran camera water in hole at 20' below ground. Very murky some bubbles at 63' and more bubbles at 27'. Discussed procedures in the event of a kick. Picked up swivel and drill collars. Put on 4th drill collar at 9:40 and drilled to 118'. Fluids began coming up around backside. Pulled out of hole. Century Wireline Services on location 11:00. Ran camera to verify clean hole. Ran geophysical logs. Designed cement job for 90' of 7" hole, calculate 19 sacks to put cement top at 29'. Rigged up cementing equipment and pumped 19 sacks at 15.8 ppg, 4.2 bbls Class G. Washed up. Off location 17:00.

Corrective Action: **Plug and abandon.**

Date: 06/09/2017