



Colorado Oil & Gas

None
None, CO 87401

P.O. Box 1979, Farmington, NM 87499
(505) 325-2627

Name: Wolcott #1
API:05-083-06341

Tower Report

Work Detail

Start	Stop	PUX	Activity
06:00 AM	08:00 AM	P	Load 33 JTs, 2 3/8' A-Plus work string. Pre trip Rig #9 and Equipment.
08:00 AM	10:00 AM	P	Travel to location.
10:00 AM	10:30 AM	P	HSM, JSA, Spot in Rig and Equipment.
10:30 AM	11:30 AM	P	RUSU, secure rig and equipment. SDFD
11:30 AM	01:00 PM	P	Travel to A-Plus yard

* P - Procedure Planned; U - Unplanned A+ issue; X - COA, Well Conditions

Crew:

Title	Name	Hours	Vehicle
Supervisor:	Stuart, Sam	7.00	75 - Crew PU
Operator:	Archuleta, George	7.00	39 - Crew PU
Derrick:	Gurule, Johnny	7.00	
Floor	Mangum, Jaben	7.00	

On Site Reps:

Name	Association	Notes
Mark Weems	COGCC	on location

Equipment:

Water Truck: #265

Pull Truck Single Axle: #400

GN Trailer: #186

PT: #315

Rig: #9

DH: #6

**Colorado Oil & Gas**

None
None, CO 87401

P.O. Box 1979, Farmington, NM 87499
(505) 325-2627

Name: Wolcott #1
API:05-083-06341

Tower Report**Cement Summary**

Plug- 1, top; inside only 65 sxs of Class B (15.6 ppg, 76.7 cf.) from 0 ft. to 234 ft.; Filled open hole, circulated 8sxs good cement to steel pit.

Plug- 2, Surface; inside only 10 sxs of Class B (15.6 ppg, 11.8 cf.) from 0 ft. to 15 ft.; ND well head, found cement down 15', filled to surface.

Work Detail

Start	Stop	PUX	Activity
05:00 AM	06:30 AM	P	Load Rig Supplies Pre Trip Equipment and ready road.
06:30 AM	08:00 AM	P	Travel to location.
08:00 AM	08:30 AM	P	HSM, JSA, Service rig and equipment
08:30 AM	09:00 AM	P	RD rig floor, dig out WH, remove 7" to 2" x-over, MU 7" X 8 5/8" x-over, and companion flange and stripping head. RU rig floor and 2 3/8" tbg equip.
09:00 AM	10:00 AM	P	Tally 2 3/8" A_Plus workstring. TIH with 8 jts tag at 234' LD 1 jt to 224'. RU PT and CMT equip. Circulate 5 BBLS water.
10:00 AM	10:30 AM	P	Plug #1 (7" csg shoe and surface plug) mix and pump 65sxs, 76.7 cuft, 15.6# B cement from 234' to surface with 8 sxs good cement circulated to pit.
10:30 AM	12:00 PM	P	LD tbg wash up PT, RD tbg equip and floor, ND WH.
12:00 PM	12:30 PM	P	RDSU
12:30 PM	01:00 PM	P	Cement down 15' in 7" csg. Top off to surface mix 10 sxs 11.8 cuft 15.6 # class B cement RD PT move off equipment.

* P - Procedure Planned; U - Unplanned A+ issue; X - COA, Well Conditions

Crew:

Title	Name	Hours	Vehicle
Supervisor:	Stuart, Sam	0.00	75 - Crew PU
Operator:	Archuleta, George	0.00	17 - Crew PU
Derrick:	Gurule, Johnny	0.00	

On Site Reps:

Name	Association	Notes
Mark Weems	COGCC	on location

**Colorado Oil & Gas**

1120 Lincoln St #801
Denver, CO 80203

P.O. Box 1979, Farmington, NM 87499
(505) 325-2627

Name: Wolcott #1
API:05-083-06341

Well Plugging Report**Work Detail**

Start	Stop	PUX	Activity
05:00 AM	07:00 AM	P	Load rig supplies, travel to location.
07:00 AM	08:00 AM	P	HSM, JSA, hot work permit.
08:00 AM	09:00 AM	P	Dig out wellhead 4' below ground level with backhoe cut off 7" csg cement at surface. Weld on dry hole marker plate. Back fill well bore. MOL
09:00 AM	09:00 AM	P	Final Report. Well Info: Latitude - 37.3445, Longitude -108.3455 Wolcott #1

* P - Procedure Planned; U - Unplanned A+ issue; X - COA, Well Conditions

Crew:

Title	Name	Hours	Vehicle
Supervisor:	Stuart, Sam	4.00	75 - Crew PU
Operator:	Archuleta, George	4.00	
Derrick:	Mangum, Jaben	4.00	
Floor	Begay, Travis	4.00	17 - Crew PU
Floor	Bluel, Noah	4.00	
Floor	Gurule, Johnny	4.00	
Floor	Marquez, Erick	4.00	44 - Crew PU

On Site Reps:

Name	Association	Notes
Mark Weems	COGCC	on location