



Colorado Oil & Gas  
None  
None, CO 87401

P.O. Box 1979, Farmington, NM 87499  
(505) 325-2627

Name: State 1-36  
API:05-083-06354

**Tower Report**

---

**Work Detail**

Start	Stop	PUX	Activity
01:00 PM	04:30 PM	P	Mobilize equipment to location
04:30 PM	05:00 PM	P	RUSU
05:00 PM	05:30 PM	P	Secure equipment and location.
05:30 PM	07:00 PM	P	Travel to A-Plus yard.

\* P - Procedure Planned; U - Unplanned A+ issue; X - COA, Well Conditions

**Crew:**

Title	Name	Hours	Vehicle
Supervisor:	Stuart, Sam	0.00	
Operator:	Archuleta, George	0.00	
Derrick:	Gurule, Johnny	0.00	

**On Site Reps:**

Name	Association	Notes
Mark Weems	COGCC	on location



Colorado Oil & Gas  
 1120 Lincoln St #801  
 Denver, CO 80203

P.O. Box 1979, Farmington, NM 87499  
 (505) 325-2627

Name: State 1-36  
 API:05-083-06354

**Tower Report**

---

**Cement Summary**

Plug - 1, Mancos, Mesa Verde, Lewis, Chacra, Pictured Cliffs, Fruitland, Kirtland, Ojo Alamo, Nacimiento, San Jose, Surface Casing Shoe, Surface top; inside only 82 sxs of Class B (15.6 ppg, 96.8 cf.) Filled open hole, circulated 10 sxs good cement to surface.  
 Plug - 2, top; 20 sxs of Class B (15.6 ppg, 23.6 cf.) ND well head found cement down 20', filled to surface

**Work Detail**

Start	Stop	PUX	Activity
09:00 AM	09:30 AM	P	HSM JSA Service rig and equipment.
09:30 AM	10:00 AM	P	Monitor well hot work permit. Weld on 4.5" collar. nipple up companion flange and stripping head.
10:00 AM	10:30 AM	P	Tally and TIH with 2 3/8" A-Plus workstring. Tag at 504' with tbg jt #16 Ld 1 jt pu 20' of subs EOT at 504'. RU pump truck.to tbg pump 8 bbls water establish circulation.
10:30 AM	11:00 AM	P	Plug #1 (6" csg shoe and surface plug) mix and pump 82 sxs, 1.18 yeild, 96.76 cuft, class B cement, 15.6# form 504' to surface.
11:00 AM	12:00 PM	P	LD tbg wash up tools, RD tbg equipment and rig floor, ND stripping head and 4.5" companion flange.
12:00 PM	12:30 PM	P	Dig out well head cut off 6" csg.
12:30 PM	01:00 PM	P	Cement down 20' in 6" csg. Top off and set DHM with 20 sxs, 23.6 cuft. 15.6# B cement.
01:00 PM	02:00 PM	P	RDSU, clean location, MOL.
02:00 PM	04:30 PM	P	Road Rig 9 and equipment to A-Plus yard.
04:30 PM	04:24 PM	P	Final Report, well info, Latitude 37.3278, Longitude -108.4619

\* P - Procedure Planned; U - Unplanned A+ issue; X - COA, Well Conditions

**Crew:**

Title	Name	Hours	Vehicle
Supervisor:	Stuart, Sam	7.50	75 - Crew PU
Operator:	Archuleta, George	7.50	
Derrick:	Begay, Travis	7.50	43 - Crew PU
Floor	Bluel, Noah	7.50	
Floor	Gurule, Johnny	7.50	
Floor	Marquez, Erick	7.50	44 - Crew PU

**On Site Reps:**

Name	Association	Notes
------	-------------	-------

Mark Weems

COGCC

on location

Worked on 05/03/2017