

**FORM
INSP**Rev
X/15

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:

06/01/2017

Submitted Date:

06/12/2017

Document Number:

666803216**FIELD INSPECTION FORM**

Loc ID 322296 Inspector Name: Murray, Richard On-Site Inspection ☐ 2A Doc Num: _____

Operator Information:OGCC Operator Number: 10043Name of Operator: MACKLEY* ARNOLD & DARLEENAddress: 4031 COUNTY RD 320City: RIFLE State: CO Zip: 81650**Status Summary:**

- ☐ THIS IS A FOLLOW UP INSPECTION
☐ FOLLOW UP INSPECTION REQUIRED
☒ NO FOLLOW UP INSPECTION REQUIRED

Findings:2 Number of Comments0 Number of Corrective Actions☐ Corrective Action Response Requested**Contact Information:**

Contact Name	Phone	Email	Comment
Murray, Richard	970-623-9782	G.Richard.Murray@state.co.us	

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
210181	WELL	DM	02/24/1961	GW	045-05076	ED T. BERNKLAU 1	DM

General Comment:Bernklau P&A project

Inspected FacilitiesFacility ID: 210181 Type: WELL API Number: 045-05076 Status: DM Insp. Status: DM**Workover**

Comment: MI flare stack, MI and RU MWS Rig #3, RU Service Unit, SICIP 45 psi, SITP 630 psi, Braden head 0 psi. RU flow line to Flare stack, Vent tbg to stack and burn off Gas for approx. ½ hr. RU line to tbg annulus and Vent and burn of gas for approximately ¾ hr. ND Well head and prep to kill well. RU pump to annulus and pumped 20 bbls water, well on a vacuum. Pumped 8 bbls water into tbg, Tbg on a vacuum. Nipple down tree, Stripped on BOP and NU same. Secured well and sdfn.

Corrective Action:

Date:

Attached DocumentsYou can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
401306404	INSPECTION SUBMITTED	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4168581