



SRC ENERGY

Operator: SRC Energy
Well Name: Loewen 11-32D
Legal: NENW, Section 32, Township 4N, Range 68W
Location: Weld County, CO
API: 05-123-33733

Deepest Water Well Within 1
Mile = 600'




Wellbore History

Spud Date: 08/10/2011
Surf Csg: 8.625", 24# @ 645' – 460 sx
Prod Csg: 4.5", 11.6# @ 7476' - 700 sx
TOC: 2695' (CBL)
Perfs: CODELL: 7295'-7319'

P&A Procedure

Set retainer@ 6950' and squeeze perfs
Set 5 sx on top of retainer (50' plug)
Pump 10 sx @ 3850' – 3950'
Cut Casing @ 695'
Pmp 295 sx @ 745' to surface

Key

-  Existing Cement Coverage
-  Retainer
-  Cement Pumped

