



## Partner Summary Report

Date: 4/19/2017

Report #: 1

Well Name: FIRESTIEN 30-12

DOL:

Spud Date: 9/6/2007

### Well Header

Well Name FIRESTIEN 30-12	API 05-123-25979	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB)	Current PBTD (mKB) ORIGINAL HOLE - 7,244.0		
Spud Date 9/6/2007	TD Date 9/9/2007	Rig Release Date 9/10/2007	First Gas Sales				
Actual Latitude (°) 40.46348000	Actual Longitude (°) -104.81822000	Quarter 3 NW	Quarter 4 NE	Section 30	Township 6	Township N/S Dir N	Range E/W Dir W

Report Start Date 4/19/2017 06:00	Report End Date 4/19/2017 18:00	Operations Summary SFTY MTG-MIRU-CHECK WHSIP(800/800 SRF 0)-LOAD WT W/150 BBLS OF FRESH H2O-GO BACK T/FIRESTEIN 30-13 & REPLACE LOCK PIN ON 5K WH-RETURN T/30-12-BLEED WELL T/WT-RC WELL W/131 BBLS TO CONTROL FLOW-FT BOP'S-ND TREE-NU BOP'S-UNLND TBG-TOOH W/230 JTS OF 2 3/8" 4.7# 8RD EUE J-55 TBG TO DERRICK-RU CHS WL-HOLD PRE-JOB SFTY MTG-RIH W/WTC CIBP-CORRELATE CCL-SET @ 7031'-POOH-RIH W/DUMP BAILER-SPOT 2 SKS ON CIBP-POOH-SI-RD WL-SECURE LOC
--------------------------------------	------------------------------------	--