



Partner Summary Report

Date: 4/20/2017

Report #: 2

Well Name: HETTINGER 24-13

DOL:

Spud Date: 6/9/2006

Well Header

Well Name HETTINGER 24-13	API 05-123-23873	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB)	Current PBTD (mKB) ORIGINAL HOLE - 7,192.0		
Spud Date 6/9/2006	TD Date 6/14/2006	Rig Release Date 6/15/2006	First Gas Sales				
Actual Latitude (°) 40.47429000	Actual Longitude (°) -104.83894000	Quarter 3 SW	Quarter 4 NE	Section 24	Township 6	Township N/S Dir N	Range E/W Dir W

Report Start Date 4/20/2017 06:00	Report End Date 4/20/2017 18:00	Operations Summary SFTY MTG-CHECK WHSIP(0/0/ SRF 25)-CONT TOO H W/100 JTS OF 2 3/8" TBG-RU CHS WL-HOLD PRE-JOB JSA-RIH W/CIBP-CORRELATE CCL-SET CIBP @ 6860'-POOH-RIH W/DUMP BAILER-SPOT 2 SKS ON CIBP-POOH-RD WL-MU NC & XN NIPPLE-TIH W/196 JTS OF 2 3/8" TBG-LND WELL W/TBG HANGER @ 6571.15 KB'-ND BOP'S-NU 5K WH-KU-CIRC HOLE-PSI TEST CIBP/WH T/1500#'S FOR 15 MINS(GOOD TEST)-RLS PSI-SI-RD-SECURE LOC
--------------------------------------	------------------------------------	--