



Partner Summary Report

Date: 4/25/2017

Report #: 1

Well Name: COUNTRY I29-04

DOL:

Spud Date: 11/6/2007

Well Header

Well Name COUNTRY I29-04	API 05-123-26421	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB)	Current PBTD (mKB) ORIGINAL HOLE - 7,231.0		
Spud Date 11/6/2007	TD Date 11/9/2007	Rig Release Date 11/10/2007	First Gas Sales				
Actual Latitude (°) 40.46432178	Actual Longitude (°) -104.80950493	Quarter 3 NW	Quarter 4 NW	Section 29	Township 6	Township N/S Dir N	Range E/W Dir W

Report Start Date 4/25/2017 06:00	Report End Date 4/25/2017 18:00	Operations Summary SFTY MTG-RU-CHECK WHSIP(550/550 SRF FLOWING H2O)-BLEED WELL T/WT-RC WELL W/100 BBLS TO REMOVE O&G-FT BOP'S-ND TREE-NU BOP'S-UNLND TBG-TALLY OOH W/220 JTS O0F 2 3/8" 4.7# 8RD EUE J-55 TBG(6757.65')-LD 10 JTS ON TRAILER-ND WASH HEAD-HOLD PRE-JOB SFTY MTG W/CHS WL-RU WL-RIH W/LEGACY CIBP-CORRELATE CCL W/MARKER JT-SET CIBP @ 7030(58' ABOVE TOP PERF)-POOH-RIH W/DUMP BAILER-SPOT 2 SKS OF CEMENT ON CIBP-POOH-RD WL-MU NC & XN NIPPLE-TIH W/220 JTS-LND WELL W/TBG HANGER @ 6771.25'-SI-DRAIN UP-SECURE LOC
--------------------------------------	------------------------------------	--