



00331793

UNITED STATES  
OF THE INTERIORSUBMIT IN TRIPPLICATE\*  
(Other instructions on re-  
verse side)

GEOLOGICAL SURVEY

Form approved.  
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

**C-02863**

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

**West Douglas Creek**

9. WELL NO.

**6**

10. FIELD AND POOL, OR WILDCAT

**West Douglas Creek - West**11. SEC., T., R., M., OR BLK. AND  
SURVEY OR AREA**Sec. 25, T2S, R 103W**

12. COUNTY OR PARISH

13. STATE

**Rio Blanco****Colorado**

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)1. OIL WELL ☐ GAS WELL ☒ OTHER

2. NAME OF OPERATOR

**Continental Oil Company**

3. ADDRESS OF OPERATOR

**P.O. Box 3312, Durango, Colorado**4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.  
See also space 17 below.)  
At surface**2073' FWL, 1950' FWL - SE/4 NW/4**

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

**6928' Gr.****6938' RB**

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

## NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETION ☐ABANDON\* ☐CHANGE PLANS ☐

## SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT\* ☐**Production String****X**(NOTE: Report results of multiple completion on Well  
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Drilled sand & shale to TD 1650'. Started out to log. Stuck drill string at 1196'. Jarred fish loose 5-23-64. Recovered fish. Conditioned hole. Ran Gamma Ray Neutron log. Ran 51 joints 4 1/2" casing, landed at 1650', and cemented with 100 sacks regular. WOC. Muddled up. Perforated 1575'-81' with 4 shots per foot. Ran 1 1/2" tubing. Swabbed well dry. Recovered drilling mud and water. Spotted 300 gals mud acid. Swabbed lead water. Well started flowing 5-30-64- 1 Mbl lead water per hour and 150 MCFD. Released rig. Recovered all lead water. Dropped from reports until MFP & flow rate have been measured.

DVR	
WKS	
HEM	
JAM	
FJP	<input checked="" type="checkbox"/>
JD	<input checked="" type="checkbox"/>
FIE	

18. I hereby certify that the foregoing is true and correct

SIGNED

**F. E. ELLIS**

TITLE

**Assistant District Manager**

DATE

**6-2-64**

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

**JUN 4 1964**

CONDITIONS OF APPROVAL, IF ANY:

\*See Instructions on Reverse Side

BEST COPY  
AVAILABLE