

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 (303) 894-2100 Fax: (303) 894-2109



FOR OGCC USE ONLY
RECEIVED
FEB 22 2002
OGCC
01078574

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of a well's completion. If the well is deepened or sidetracked, a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report). If the well has been plugged, submit Form 6 (Well Abandonment Report).

Complete the Attachment Checklist

1. OGCC Operator Number: 69175		4. Contact Name and Telephone Name: Eric R. Stearns, VP of Exploration & Development Phone: (304) 842-3597 Fax: (304) 842-0913		<table border="1"> <tr><td>Survey Plat</td><td></td><td></td></tr> <tr><td>Directional Survey</td><td></td><td></td></tr> <tr><td>Surface Equip. Diagram</td><td></td><td></td></tr> <tr><td>Technical Info. Page</td><td></td><td></td></tr> <tr><td>Other</td><td></td><td></td></tr> </table>		Survey Plat			Directional Survey			Surface Equip. Diagram			Technical Info. Page			Other		
Survey Plat																				
Directional Survey																				
Surface Equip. Diagram																				
Technical Info. Page																				
Other																				
2. Name of Operator: Petroleum Development Corporation		3. Address: 103 East Main Street, P.O. Box 26 City: Bridgeport State: WV ZIP: 26330		15. Well Classification <input type="checkbox"/> Dry <input checked="" type="checkbox"/> Oil <input type="checkbox"/> Gas <input type="checkbox"/> Coalbed <input type="checkbox"/> Stratigraphic <input type="checkbox"/> Disposal <input type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Gas Storage <input type="checkbox"/> Observation <input type="checkbox"/> Other:																
5. API Number: 05-123-20483-00		6. County: WELD		7. Well Name: J & L Farms																
8. Location (QtrQtr, Sec, Twp, Rng, Meridian):		Well Number: #29B		9. Was a directional survey run? <input type="checkbox"/> Y <input checked="" type="checkbox"/> N																
Footage at Surface: 1322' FSL, 1315' FWL		Field Number: 90750		10. Field Name: WATTENBERG																
If directional, footage at Top of Prod. Zone:		11. Federal, Indian or State lease Number:		12. Spud Date: 9/10/01																
If directional, footage at Bottom Hole:		12. Date TD: 9/15/01		14. Date Completed or D&A: 9/21/01																
16. Total Depth: MD 6986' TVD (same)		17. Plug Back Total: MD 6950' TVD same		19. Elevations GR 4660' KB 4670'																
18. Was a Mud Log Run? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		19. Elevations		20. List Electric Log Run: GR, IND, DENSITY, NEUTRON																
One copy of all electronic and mud logs must be submitted.																				

CASING, LINER and CEMENT

Submit contractor's cement job summary for each string cemented

String	Hole Size	Csg/Liner Size	Csg/Liner Wt (Lbs.)	Csg/Liner Top	Csg/Tool Setting Depth	No. of Sacks	Cement Interval		Identify Method	
							Top	Bottom	CBL	Calc
SURF	12 1/4"	8 5/8"	24#	0'	398'	290	0'	398'	<input type="checkbox"/>	XX
PROD	7 7/8"	4 1/2"	10.5#	0'	6950'	155 "G"	6252'	6950'	XX	<input type="checkbox"/>
Stage Cement										
PROD	7 7/8"	4 1/2"	10.5#	0'	6950'	306 lite	2808'	6252'	XX	<input type="checkbox"/>
Stage Cement										
Stage Cement										
Stage Cement										
Stage Cement										
Stage Cement										
Stage Cement										

FORMATION LOG INTERVALS and TEST ZONES

Formation	Measured Depth		Check if applies		Comments
	Top	Bottom	DST	Cored	
GREELEY	2520'		<input type="checkbox"/>	<input type="checkbox"/>	
PARKMAN	3525'		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	3980'		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	4420'		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6416'		<input type="checkbox"/>	<input type="checkbox"/>	
FT. HAYES	6712'		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	6757'		<input type="checkbox"/>	<input type="checkbox"/>	
CARLILE	6774'		<input type="checkbox"/>	<input type="checkbox"/>	
GREENHORN	6790'		<input type="checkbox"/>	<input type="checkbox"/>	
TD	6986'		<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete:

Print Name: Alan H Smith

Signed: [Signature] Title: Geologist Date: 1/01/02