

Donnelly Casing Pulling Co.

Phone 522-1410

P.O. Box 791
Sterling, Colorado 80751

RECEIVED

JAN 23 1978

Bob Donnelly

SOLD Vessels Oil & Gas Company
TO 600 South Cherry St., Suite 1220
Denver, Colorado 80222

COLO. OIL & GAS CONS. COMM.
INVOICE DATE 1-9-78

WELL O H D #1

INVOICE NO. 154

1860' 4 1/2" OD Casing @	40¢ per foot	\$ 746.00
Day Work, 54 hours @	\$25.00 per hour	1350.00
Water Truck, 12 hours @	\$20.00 per hour	240.00
7 shots, first 3 free, additional 4 @	\$10.00 per shot	40.00
Cement, 30 sacks @	\$4.50 each + tax	139.05
Pump, 2 jobs @	\$350.00 per job	700.00
Tanks, Inc.	ticket enclosed	146.00
Adams Transit Mix	tickets enclosed	585.79
		<u>\$3946.84</u>

DATE	DAY WORK	REMARKS
11-28-77	2 hours	Moved unit in. Dug deadmen.
11-29-77	8 hours	Finished digging deadmen. Dug cellar. Waited for well to bleed off.
11-30-77	9 hours	Pumped 100 bbls. water to kill well. Water truck, 7 hours. Pump job.
12- 1-77	8 hours	Pumped 50 bbls. water. Ran sand 8354' to 8300'. Set in floor. Worked pipe to 22".
12- 2-77	9 hours	Dumped 5 sacks cement on sand. Worked pipe to 24". Ran shots to 3005' and 2820'. Worked pipe to 26". Ran shots to 2610' and 2400'.
12- 5-77	8 hours	Worked pipe to 28". Pumped 10 bbls. water. Ran shots to 2210', 2000' and 1830'. Pulled 2 joints.
12- 6-77	6 hours	Pulled pipe to 1300'. Pumped 175 sacks cement. Pulled pipe, 59 total. Water truck, 5 hours. Pump job.
12- 7-77	4 hours	Tore down floor. Set 15 sacks cement in and out of surface. Filled with mud to 35'. Set 10 sacks cement to 5' below ground level.

WELL COMPLETE

THANK YOU



00380391