

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

401304214

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10071

Contact Name: BRADY RILEY

Name of Operator: BARRETT CORPORATION* BILL

Phone: (303) 3128115

Address: 1099 18TH ST STE 2300

Fax:

City: DENVER

State: CO

Zip: 80202

API Number 05-123-44254-00

County: WELD

Well Name: CVR

Well Number: 5-63-32-6457B2B

Location: QtrQtr: NWSW Section: 32 Township: 5N Range: 63W Meridian: 6

Footage at surface: Distance: 1392 feet Direction: FSL Distance: 230 feet Direction: FWL

As Drilled Latitude: 40.352500 As Drilled Longitude: -104.468628

GPS Data:

Date of Measurement: 04/04/2017 PDOP Reading: 1.4 GPS Instrument Operator's Name: JARED CHRISTOPHER

** If directional footage at Top of Prod. Zone Dist.: 10 feet. Direction: FSL Dist.: 585 feet. Direction: FWL

Sec: 32 Twp: 5N Rng: 63W

** If directional footage at Bottom Hole Dist.: 27 feet. Direction: FSL Dist.: 504 feet. Direction: FEL

Sec: 33 Twp: 5N Rng: 63W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 03/31/2017 Date TD: 04/14/2017 Date Casing Set or D&A: 04/15/2017

Rig Release Date: 05/21/2017 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 16590 TVD** 6382 Plug Back Total Depth MD 16581 TVD** 6382

Elevations GR 4581 KB 4601

Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

MWD/LWD; CBL; MUD; INDUCTION (OPEN HOLE LOGS) WAS RAN ON CVR 5-63-32-6457D2 (API 05-123-44253)

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	9+5/8	36	0	837	220	0	837	VISU
1ST	8+3/4	7	26	0	6,985	700	780	6,985	CBL
1ST LINER	6+1/8	4+1/2	11.6	6216	16,585	678	6,216	16,585	CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHANNON	5,157		NO	NO	
SHARON SPRINGS	6,483		NO	NO	
NIOBRARA	6,623		NO	NO	

Comment:

PBTD is taken from the float collar set depth

OPEN HOLE LOGS (IND) FOR THIS PAD ARE SUBMITTED UNDER THE CVR 5-63-32-6457D2 (API 05-123-44253)

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: BRADY RILEY

Title: PERMIT ANALYST

Date: _____

Email: BRILEY@BILLBARRETTCORP.COM

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
401340531	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
401340534	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
401340537	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401340543	PDF-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401340565	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401340569	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401340575	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401340577	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)