

On July 20, 2017 COGCC Environmental Staff (Alex Fischer) conducted an environmental field inspection of DIVERSIFIED ENERGY LLC (Diversified) Bingham Location ID: 313094. The INSP included the lease road, API 08-06954, the tank battery, and what appeared to be the formal land treatment area. Weather was sunny to partially cloudy and temperature app mid 60s degree F and wind from the south. Well was not producing at time of inspection. *For the most recent Field and Environmental Field inspection report of this facility, please refer to document # 685100085. The overall inspection status shall remain the same as that document until all corrective actions have been completed.* The following is a summary:

**Well head:**

Vegetation (weeds) growth around pump jack and propane tank.

**Tank Battery:**

One (1) 300-bbl crude tank labeled and placard.

One (1) 300-bbl crude tank labeled and placard.

Tank battery bermed with vegetation (weeds). Plastic liner incorporated into recent berm dirt work.

**Land Treatment Area:**

The appr 30'x 50' x 3' in depth land treatment area is for the most part removed.

Plastic liner pieces are incorporated in the area where the treatment area was located.

Stained soil material with a hydrocarbon odor was noted.

**Pit Facility ID 285519:**

Aprr 60' x 80' x 10' deep pit located north of well. Appears to have material, gray in color with sfc flow into the pit from the south. Fenced with 3' hog wire and one strand of barbed wire on steel "T" posts.

**Location:**

The Location was recently graded and now has plastic liner pieces throughout the entire Location.

**Lease Road:**

The lease road was recently graded and has plastic liner pieces throughout the entire roadway up to the Location.

Stained soil material with a hydrocarbon odor was noted.

**Corrective Actions (CAs):**

Address the CAs outlined in the previous Inspection Report, Document Number 685100085.

Comply with the COAs on Form 27, Document Number 401283384.

**By August 4, 2017** Comply with Rule 603.f using the Rule 603.f guidance document for further details. (Including the removal of ALL plastic liner material throughout Location, lease road, and berms).

**By August 4, 2017** Comply with Rule 603.f using the Rule 603.f guidance document for further details. (Including the management of weeds).

**By August 4, 2017** Provide waste transportation and final disposition information in accordance with 907.b.(2) for all E&P waste transported off site.

**By July 26, 2017** remediate the oily stains on Location, the lease road beneath valves, fittings, and unions at well head and tanks. Properly treat or dispose of oily waste in accordance with Rule 907.e.