

API:	05-123-07875	KB ELEVATION:	4830	QTR-QTR:	SESW
WELL NAME:	FLORENCE BERRY UNIT 1	GROUND LEVEL:	4818	SECTION:	26
COUNTY:	WELD	MD:	7922	TOWNSHIP:	3N
LATITUDE:	40.1922935	PBMD:	7873	RANGE:	67W
LONGITUDE:	-104.8616181	CREATED BY:	D. HASZ		
		DATE:	7/24/2017		

Existing		DATUM: RKB KB=12'		Proposed	
Hole Size/Depth	12 1/4" - 219'		To Surf.		
			80'		
<u>Surface Casing</u>				169'	TOC in S.C.
Casing Size/Depth: 8-5/8", 24#/ft @	219'				
			40 sx 1.5 yld		
Stage Tool / BOC (est.)	585'			600'	Top Sq Perfs
			630'		
Fox Hills Formation Marker	899'		125 sx 1.51 yld	1000'	Bot Sq Perfs
			3 bbls	3870'	TOC inside csg
				4030'	Top Sq Perfs
Sussex			4060'		
Top	4232'		135 sx		
Base	4438'		1.51 yld	4435'	Bot Sq Perfs
NOT Productive within 1 mile					
Shannon	4789'				
NOT Productive within 1 mile*					
			3 bbls	6495'	TOC inside csg
				6655'	Top Sq Perfs
			6685'		
Niobrara Top	7057'		210 sx		
			1.51 yld	7300'	Bot Sq Perfs
			2 sx		
			7710'		
J Sand Perfs	7764' - 7802'				
<u>Production Casing/Hole</u>					
Casing Size/Depth	4-1/2", 10.5 & 11.6#/ft @	7921'			
Hole Size/Depth	7 7/8" (bit size) @	7922'			

Existing Cement
New CICR
Existing CICR
New CIBP
Existing CIBP
New Cement
Sand Plug
Existing Mud

*Nearby Mayer Walter B-1 SNSD abandoned in 2004