

DRILLING COMPLETION REPORT

Document Number:
401364475

Date Received:

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

OGCC Operator Number: 47120 Contact Name: Jennifer Thomas
 Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6808
 Address: P O BOX 173779 Fax: _____
 City: DENVER State: CO Zip: 80217-

API Number 05-123-44316-00 County: WELD
 Well Name: BUTTERBALL Well Number: 40N-34HZ
 Location: QtrQtr: NENE Section: 10 Township: 2N Range: 67W Meridian: 6
 Footage at surface: Distance: 578 feet Direction: FNL Distance: 674 feet Direction: FEL
 As Drilled Latitude: 40.158270 As Drilled Longitude: -104.869545

GPS Data:
 Date of Measurement: 04/05/2017 PDOP Reading: 2.5 GPS Instrument Operator's Name: ROB WILSON

** If directional footage at Top of Prod. Zone Dist.: 159 feet. Direction: FSL Dist.: 279 feet. Direction: FEL
 Sec: 3 Twp: 2N Rng: 67W
 ** If directional footage at Bottom Hole Dist.: 2562 feet. Direction: FSL Dist.: 275 feet. Direction: FEL
 Sec: 34 Twp: 3N Rng: 67W

Field Name: WATTENBERG Field Number: 90750
 Federal, Indian or State Lease Number: _____

Spud Date: (when the 1st bit hit the dirt) 04/30/2017 Date TD: 05/20/2017 Date Casing Set or D&A: 05/21/2017
 Rig Release Date: 06/09/2017 Per Rule 308A.b.

Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

Total Depth MD 15425 TVD** 7236 Plug Back Total Depth MD 15366 TVD** 7235
 Elevations GR 4916 KB 4936 **Digital Copies of ALL Logs must be Attached per Rule 308A**

List Electric Logs Run:
CBL, GR, CNL RUN ON BUTTERBALL 40C-34HZ, API 05-123-44319

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.1	0	100	64	0	100	VISU
SURF	13+1/2	9+5/8	36	0	1,843	713	0	1,843	VISU
1ST	7+7/8	5+1/2	17	0	15,415	1,580	96	15,415	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,407				
SHARON SPRINGS	7,254				
NIOBRARA	7,451				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted. Per Rule 371.p Exception, compensated neutron logs have been run on the BUTTERBALL 40C-34HZ well (API 05-123-44319).

The Top of Productive Zone provided is an estimate based on the landing point at 7667' MD.

Completion is estimated for Q1, 2018

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Jennifer Thomas

Title: Regulatory Analyst

Date: _____

Email: jennifer.thomas@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
401364587	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
401364584	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
Other Attachments			
401364579	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401364580	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401364581	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401364582	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401364583	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)