



## Partner Summary Report

Date: 6/12/2017

Report #: 1

Well Name: STATE M36-03

DOL:

Spud Date: 11/17/2005

### Well Header

Well Name STATE M36-03	API 05-123-23254	County/Parish WELD	State/Province COLORADO	Total Depth All (TVD) (ftKB)	Current PBTD (mKB) ORIGINAL HOLE - 7,612.0		
Spud Date 11/17/2005	TD Date 11/21/2005	Rig Release Date 11/22/2005	First Gas Sales				
Actual Latitude (°) 40.44874341	Actual Longitude (°) -104.84440935	Quarter 3 NE	Quarter 4 NW	Section 36	Township 6	Township N/S Dir N	Range E/W Dir W

Job: OTHER , Job Start Date: 6/12/2017 07:00

Report Start Date 6/12/2017 07:00	Report End Date 6/12/2017 23:30	Operations Summary MON: RODE RIG TO LOC.HELD SAFETY MEETING.IWP-TBG-0# CSG-0# SURF-CSG-0.BULLS EYE FLOW BACK ON LOCATION. FOSSIL LOGISTICS LLC DELIVERING BASE BEAM,PUMP,WORK TANK.DELIVERED TRANS 40 BBL'S 2% KCL & BIO H2O FROM ARD PC C06-18D.PLACED LOTO.FUNCTION TEST 5K BOP.BOTH BLIND RAMS PIPE RAMS PROPER WORKING ORDER FOR 2 3/8" TBG.R/U LEED WSU #719.N/D MASTER VALVE TOP FLANGE. N/U 5K BOP. POOH S/B 190 JT'S 2 3/8' 4.7# J-55 TBG.L/D 23 JT'S ONTO SILLS.R/U CASD HOLE SOLUTIONS.RIH 4 1/2" CIBP SET 6978' CORRELATED USING CBL LOG DATED 12-10-2005. SET PLUG PULLED UP RETAGGED PLUG IS THERE.POOH SETTING TOOL.RIH DUMP BAIL 3 SAC'S CEMENT 39' CEMENT TOP OF PLUG.POOH L/D DUMP BAILER.R/D CHS.RIH 204 JT'S HANG OFF OPEN ENDED @ 6729.49' KB 209.51' ABOVE TOC. N/D 5K BOP.N/U TOP FLANGE XN NIPPLE NEW 2 3/8" MASTER VALVE.CHANGED OUT 3K BALON VALVES TO 5K BALONS EXTRA HEAVY DUTY NIPPLES.NPT ON LOC 80 BBL'S 2% KCL BIO H2O.USING RIG PUMP CIRC HOLE BTM'S UP 80 BBL'S.BROUGHT BACK QUITE A BIT OF OIL/ GAS .PRESSURED UP 1000PSI HELD 15 MIN.GOOD TEST NO LOSS.OFFICE
--------------------------------------	------------------------------------	--