

FORM  
2

Rev  
08/16

## State of Colorado

### Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401148329

Date Received:

11/14/2016

#### APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Launer Well Number: 3  
Name of Operator: EXTRACTION OIL & GAS INC COGCC Operator Number: 10459  
Address: 370 17TH STREET SUITE 5300  
City: DENVER State: CO Zip: 80202  
Contact Name: Jeff Annable Phone: (303)928-7128 Fax: (303)218-5678  
Email: regulatory@petro-fs.com

#### RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20130028

#### WELL LOCATION INFORMATION

QtrQtr: SESE Sec: 26 Twp: 7N Rng: 67W Meridian: 6

Latitude: 40.540258

Longitude: -104.852038

Footage at Surface: 861 Feet FSL 301 Feet FEL

Field Name: WATTENBERG Field Number: 90750

Ground Elevation: 4930 County: WELD

GPS Data:

Date of Measurement: 08/29/2014 PDOP Reading: 1.5 Instrument Operator's Name: Ben Hardenbergh

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2141 FSL 592 FEL 2204 FSL 2561 FEL 2204  
Sec: 26 Twp: 7N Rng: 67W Sec: 27 Twp: 7N Rng: 67W

#### LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 6 North, Range 67W, 6th PM  
Section 26: Part of the SE4

See attached lease map.

Total Acres in Described Lease: 78 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 632 Feet  
Building Unit: 1118 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 282 Feet  
Above Ground Utility: 363 Feet  
Railroad: 5280 Feet  
Property Line: 301 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 150 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

Nearest wellbore permitted or completed in the same formation is the Frye North 3 API #05-123-41076 (Common source NBRR well).

NBRR: Proposed Spacing Unit is described as  
T7N,R67W:  
Sec 26 - N2S2  
Sec 27 - N2SE4, SENW, NESW, SWNE

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		360	GWA

## DRILLING PROGRAM

Proposed Total Measured Depth: 14758 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 162 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted?

Reuse Facility ID:  or Document Number:

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	42	0	80	100	80	0
SURF	12+1/4	9+5/8	36	0	1500	400	1500	0
1ST	7+7/8	5+1/2	20	0	14758	1390	14758	1500

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments Letter to the Director for COGCC Rule 318A.a. Exception Location for GWA Window, attached as the Exception Loc Request.

Waiver for COGCC Rule 318A.a. is highlighted on page 10 of the SUA.

Nearest permitted or existing wellbore belonging to another operator is the 05-123-05318, FRED BRUNNER JR #2, CHEVRON USA, PA.

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jeff Annable

Title: Regulatory Analyst Date: 11/14/2016 Email: regulatory@petro-fs.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  \_\_\_\_\_ Director of COGCC Date: 8/11/2017

Expiration Date: 08/10/2019

### API NUMBER

05 123 45175 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### COA Type

### Description

	This Permit to Drill is approved subject to all the BMPs and COAs on the most recently approved Form 2A and any subsequently approved Form 4 for the Oil and Gas Location. The most recently approved Form 2A and any subsequent Form 4s containing applicable COAs for this location shall be posted onsite during construction, drilling, and completions operations.
	Operator agrees to comply with the DJ Basin Horizontal Offset Policy to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, submit Form 42(s) ("OFFSET MITIGATION COMPLETED") for the remediated well(s), referencing the API Number of the proposed horizontal well, to report that appropriate mitigation was completed prior to the hydraulic stimulation of the proposed horizontal well. Operator acknowledges the proximity of the following offset well(s) of concern: 05-123-05327, RUMER HALL #1 05-123-05318, FRED BRUNNER JR #2
	Bradenhead tests shall be performed and reported according to the following schedule and Form 17 submitted within 10 days of each test.: 1) All: Within 60 days of rig release, prior to stimulation. 2) Delayed completion: 6 months after rig release, prior to stimulation. 3) All: Within 30 days of first production, as reported on Form 5A.
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Provide cement coverage to a minimum of 200' above Niobrara, and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.

## Best Management Practices

No	BMP/COA Type	Description
1	Planning	<p>Blowout Prevention Equipment ("BOPE"): A double ram and annular preventer will be used during drilling. Stabbing valves shall be installed in the event of reverse circulation and shall be prior tested with low and high pressure fluid.</p> <p>Backup stabbing valves will be required on well servicing operations during reverse circulation. Valves shall be pressure tested before each well servicing operation using both low-pressure air and high-pressure fluid.</p>
2	Construction	All guy line anchors left buried for future use shall be identified by a marker of bright color not less than four (4) feet in height and not greater than one (1) foot east of the guy line anchor.
3	Emissions mitigation	<p>Green Completions - Emission Control System. Test separators and associated flow lines and sand traps shall be installed on-site to accommodate green completions techniques pursuant to COGCC Rules.</p> <p>Operator will bring a new or expand existing gas sales lines, in a timely manner, to send salable quality gas immediately down the sales line.</p>
4	Odor mitigation	Oil & gas facilities and equipment shall be operated in such a manner that odors and dust do not constitute a nuisance or hazard to public welfare. Operator is in the process of implementing a new base fluid for Oil Base Mud systems. The aromatics and BTEX concentrations are much less than that of generic diesel. With these two things being the major contributors to the odor from diesel, this should lead to less odor at the drill site caused by OBM.
5	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.
6	Drilling/Completion Operations	Operator acknowledges and will comply with COGCC policy for Bradenhead Monitoring during Hydraulic Fracturing treatments in the Greater Wattenberg Area dated May 29, 2012.
7	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.
8	Drilling/Completion Operations	BOPE testing for drilling operations. Upon initial rig-up and at least once every thirty (30) days during drilling operations thereafter, pressure testing of the casing string and each component of the blowout prevention equipment including flange connections shall be performed to seventy percent (70%) of working pressure or seventy percent (70%) of the internal yield of casing, whichever is less. Pressure testing shall be conducted and the documented results shall be retained by the operator for inspection by the Director for a period of one (1) year. Activation of the pipe rams for function testing shall be conducted on a daily basis when practicable.
9	Drilling/Completion Operations	Operator will be utilizing a closed loop system.
10	Drilling/Completion Operations	All loadlines shall be bull plugged or capped.

Total: 10 comment(s)

### **Applicable Policies and Notices to Operators**

Policy
Notice Concerning Operating Requirements for Wildlife Protection. <a href="http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf">http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf</a>
Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area. <a href="http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf">http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf</a>

### **Attachment Check List**

<b><u>Att Doc Num</u></b>	<b><u>Name</u></b>
401148329	FORM 2 SUBMITTED
401148486	WELL LOCATION PLAT
401148488	EXCEPTION LOC REQUEST
401148489	PROPOSED SPACING UNIT
401148490	SURFACE AGRMT/SURETY
401148491	DEVIATED DRILLING PLAN
401148492	DIRECTIONAL DATA
401149278	OffsetWellEvaluations Data
401149281	LEASE MAP
401374129	OFFSET WELL EVALUATION

Total Attach: 10 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Off hold--final review complete. Agreement between Extraction and Great Western completed. Corrected distance to lease line to 0'.	08/10/2017
Permit	ON HOLD: waiting for trade to be finalized--probably mid-summer.	04/27/2017
Permit	Final Review Completed.	04/12/2017
Engineer	Operator Comments: Corrected "Nearest permitted or existing wellbore belonging to another operator".	04/10/2017
Engineer	On the Drilling Program "Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells" appear to be incorrect. Requested operator review and provide correct distance.	04/06/2017
Permit	Open Hole Logging BMP submitted by operator. Permitting Review Complete.	03/20/2017
Permit	Passed completeness.	11/17/2016

Total: 7 comment(s)