

# **TEP Rocky Mountain LLC**

**Garfield County, CO NAD83**

**PA 23-26 Pad**

**PA 331-26 - Slot B4**

**OH**

**Plan: Plan #1**

## **Standard Planning Report**

**10 July, 2017**



**N/A**  
Planning Report

<b>Database:</b>	EDM_PRO	<b>Local Co-ordinate Reference:</b>	Well PA 331-26 - Slot B4
<b>Company:</b>	TEP Rocky Mountain LLC	<b>TVD Reference:</b>	WELL @ 5658.0ft (Original Well Elev)
<b>Project:</b>	Garfield County, CO NAD83	<b>MD Reference:</b>	WELL @ 5658.0ft (Original Well Elev)
<b>Site:</b>	PA 23-26 Pad	<b>North Reference:</b>	True
<b>Well:</b>	PA 331-26	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #1		

<b>Project</b>	Garfield County, CO NAD83		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	Colorado Central Zone		

Site		PA 23-26 Pad			
Site Position:		Northing:	1,614,400.30 ft	Latitude:	39° 29' 39.674 N
From:	Map	Easting:	2,303,981.10 ft	Longitude:	107° 57' 59.978 W
Position Uncertainty:	0.0 ft	Slot Radius:	13.200 in	Grid Convergence:	-1.56 °

Well	PA 331-26 - Slot B4, B4					
Well Position	+N/-S	-10.9 ft	Northing:	1,614,390.02 ft	Latitude:	39° 29' 39.567 N
	+E/-W	-22.1 ft	Easting:	2,303,958.74 ft	Longitude:	107° 58' 0.259 W
Position Uncertainty		0.0 ft	Wellhead Elevation:		Ground Level:	5,637.0 ft

<b>Wellbore</b>	OH				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2015	5/19/2017	9.70	65.59	51,543.20165758

Design	Plan #1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(ft)	(ft)	(ft)	(°)
	0.0	0.0	0.0	24.30

<b>Plan Survey Tool Program</b>	<b>Date</b>	7/10/2017			
<b>Depth From (ft)</b>	<b>Depth To (ft)</b>	<b>Survey (Wellbore)</b>	<b>Tool Name</b>	<b>Remarks</b>	
1	0.0	9,378.9 Plan #1 (OH)	SDI MWD		
			SDI MWD - Standard ver 1.0.1		

<b>Plan Sections</b>										
<b>Measured Depth (ft)</b>	<b>Inclination (°)</b>	<b>Azimuth (°)</b>	<b>Vertical Depth (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Dogleg Rate (°/100usft)</b>	<b>Build Rate (°/100usft)</b>	<b>Turn Rate (°/100usft)</b>	<b>TFO (°)</b>	<b>Target</b>
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
800.0	0.00	0.00	800.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,133.3	40.00	24.30	2,027.6	407.2	183.8	3.00	3.00	0.00	24.30	
4,897.0	40.00	24.30	4,144.8	2,026.3	914.8	0.00	0.00	0.00	0.00	
7,563.6	0.00	0.00	6,600.0	2,840.7	1,282.5	1.50	-1.50	0.00	180.00	
9,379.6	0.00	0.00	8,416.0	2,840.7	1,282.5	0.00	0.00	0.00	0.00	PBHL(PA 331-26)



**N/A**  
Planning Report

<b>Database:</b>	EDM_PRO	<b>Local Co-ordinate Reference:</b>	Well PA 331-26 - Slot B4
<b>Company:</b>	TEP Rocky Mountain LLC	<b>TVD Reference:</b>	WELL @ 5658.0ft (Original Well Elev)
<b>Project:</b>	Garfield County, CO NAD83	<b>MD Reference:</b>	WELL @ 5658.0ft (Original Well Elev)
<b>Site:</b>	PA 23-26 Pad	<b>North Reference:</b>	True
<b>Well:</b>	PA 331-26	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N-S (ft)	+E-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	3.00	24.30	900.0	2.4	1.1	2.6	3.00	3.00	0.00
1,000.0	6.00	24.30	999.6	9.5	4.3	10.5	3.00	3.00	0.00
1,100.0	9.00	24.30	1,098.8	21.4	9.7	23.5	3.00	3.00	0.00
9 5/8"									
1,200.0	12.00	24.30	1,197.1	38.0	17.2	41.7	3.00	3.00	0.00
1,300.0	15.00	24.30	1,294.3	59.3	26.8	65.1	3.00	3.00	0.00
1,400.0	18.00	24.30	1,390.2	85.2	38.5	93.5	3.00	3.00	0.00
1,500.0	21.00	24.30	1,484.4	115.6	52.2	126.9	3.00	3.00	0.00
1,600.0	24.00	24.30	1,576.8	150.5	67.9	165.1	3.00	3.00	0.00
1,700.0	27.00	24.30	1,667.1	189.7	85.7	208.2	3.00	3.00	0.00
1,800.0	30.00	24.30	1,754.9	233.2	105.3	255.9	3.00	3.00	0.00
1,900.0	33.00	24.30	1,840.2	280.8	126.8	308.1	3.00	3.00	0.00
2,000.0	36.00	24.30	1,922.6	332.4	150.1	364.8	3.00	3.00	0.00
2,100.0	39.00	24.30	2,001.9	387.9	175.1	425.6	3.00	3.00	0.00
2,133.3	40.00	24.30	2,027.6	407.2	183.8	446.8	3.00	3.00	0.00
2,200.0	40.00	24.30	2,078.7	446.3	201.5	489.7	0.00	0.00	0.00
2,300.0	40.00	24.30	2,155.3	504.9	227.9	554.0	0.00	0.00	0.00
2,400.0	40.00	24.30	2,231.9	563.5	254.4	618.2	0.00	0.00	0.00
2,500.0	40.00	24.30	2,308.5	622.0	280.8	682.5	0.00	0.00	0.00
2,600.0	40.00	24.30	2,385.1	680.6	307.3	746.8	0.00	0.00	0.00
2,700.0	40.00	24.30	2,461.7	739.2	333.7	811.1	0.00	0.00	0.00
2,800.0	40.00	24.30	2,538.3	797.8	360.2	875.3	0.00	0.00	0.00
2,825.7	40.00	24.30	2,558.0	812.8	367.0	891.8	0.00	0.00	0.00
Wasatch G									
2,900.0	40.00	24.30	2,615.0	856.4	386.6	939.6	0.00	0.00	0.00
2,904.0	40.00	24.30	2,618.0	858.7	387.7	942.2	0.00	0.00	0.00
Wasatch G Base									
3,000.0	40.00	24.30	2,691.6	915.0	413.1	1,003.9	0.00	0.00	0.00
3,100.0	40.00	24.30	2,768.2	973.5	439.5	1,068.2	0.00	0.00	0.00
3,200.0	40.00	24.30	2,844.8	1,032.1	466.0	1,132.4	0.00	0.00	0.00
3,300.0	40.00	24.30	2,921.4	1,090.7	492.4	1,196.7	0.00	0.00	0.00
3,400.0	40.00	24.30	2,998.0	1,149.3	518.9	1,261.0	0.00	0.00	0.00
3,500.0	40.00	24.30	3,074.6	1,207.9	545.3	1,325.3	0.00	0.00	0.00
3,600.0	40.00	24.30	3,151.2	1,266.5	571.8	1,389.6	0.00	0.00	0.00
3,700.0	40.00	24.30	3,227.8	1,325.0	598.2	1,453.8	0.00	0.00	0.00
3,800.0	40.00	24.30	3,304.4	1,383.6	624.7	1,518.1	0.00	0.00	0.00
3,900.0	40.00	24.30	3,381.0	1,442.2	651.1	1,582.4	0.00	0.00	0.00
4,000.0	40.00	24.30	3,457.6	1,500.8	677.6	1,646.7	0.00	0.00	0.00
4,100.0	40.00	24.30	3,534.2	1,559.4	704.0	1,710.9	0.00	0.00	0.00
4,200.0	40.00	24.30	3,610.8	1,618.0	730.5	1,775.2	0.00	0.00	0.00
4,300.0	40.00	24.30	3,687.4	1,676.5	756.9	1,839.5	0.00	0.00	0.00
4,400.0	40.00	24.30	3,764.0	1,735.1	783.4	1,903.8	0.00	0.00	0.00
4,500.0	40.00	24.30	3,840.7	1,793.7	809.8	1,968.0	0.00	0.00	0.00
4,600.0	40.00	24.30	3,917.3	1,852.3	836.3	2,032.3	0.00	0.00	0.00



**N/A**  
Planning Report

<b>Database:</b>	EDM_PRO	<b>Local Co-ordinate Reference:</b>	Well PA 331-26 - Slot B4
<b>Company:</b>	TEP Rocky Mountain LLC	<b>TVD Reference:</b>	WELL @ 5658.0ft (Original Well Elev)
<b>Project:</b>	Garfield County, CO NAD83	<b>MD Reference:</b>	WELL @ 5658.0ft (Original Well Elev)
<b>Site:</b>	PA 23-26 Pad	<b>North Reference:</b>	True
<b>Well:</b>	PA 331-26	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,700.0	40.00	24.30	3,993.9	1,910.9	862.7	2,096.6	0.00	0.00	0.00
4,800.0	40.00	24.30	4,070.5	1,969.5	889.2	2,160.9	0.00	0.00	0.00
4,897.0	40.00	24.30	4,144.8	2,026.3	914.8	2,223.2	0.00	0.00	0.00
4,900.0	39.95	24.30	4,147.1	2,028.0	915.6	2,225.2	1.50	-1.50	0.00
5,000.0	38.45	24.30	4,224.6	2,085.7	941.6	2,288.4	1.50	-1.50	0.00
5,100.0	36.95	24.30	4,303.7	2,141.4	966.8	2,349.5	1.50	-1.50	0.00
5,200.0	35.45	24.30	4,384.4	2,195.2	991.1	2,408.6	1.50	-1.50	0.00
5,300.0	33.95	24.30	4,466.6	2,247.1	1,014.5	2,465.5	1.50	-1.50	0.00
5,400.0	32.45	24.30	4,550.2	2,297.0	1,037.0	2,520.3	1.50	-1.50	0.00
5,500.0	30.95	24.30	4,635.3	2,344.9	1,058.7	2,572.8	1.50	-1.50	0.00
5,600.0	29.45	24.30	4,721.7	2,390.8	1,079.4	2,623.1	1.50	-1.50	0.00
5,658.6	28.57	24.30	4,773.0	2,416.7	1,091.1	2,651.6	1.50	-1.50	0.00
Ohio Creek									
5,700.0	27.95	24.30	4,809.5	2,434.5	1,099.1	2,671.2	1.50	-1.50	0.00
5,800.0	26.45	24.30	4,898.4	2,476.2	1,117.9	2,716.9	1.50	-1.50	0.00
5,860.8	25.54	24.30	4,953.0	2,500.5	1,128.9	2,743.5	1.50	-1.50	0.00
Upper MVRD									
5,900.0	24.95	24.30	4,988.5	2,515.7	1,135.8	2,760.2	1.50	-1.50	0.00
6,000.0	23.45	24.30	5,079.7	2,553.1	1,152.7	2,801.2	1.50	-1.50	0.00
6,100.0	21.95	24.30	5,171.9	2,588.3	1,168.5	2,839.8	1.50	-1.50	0.00
6,200.0	20.45	24.30	5,265.2	2,621.2	1,183.4	2,876.0	1.50	-1.50	0.00
6,300.0	18.95	24.30	5,359.3	2,652.0	1,197.3	2,909.7	1.50	-1.50	0.00
6,400.0	17.45	24.30	5,454.3	2,680.5	1,210.1	2,941.0	1.50	-1.50	0.00
6,500.0	15.95	24.30	5,550.1	2,706.6	1,222.0	2,969.7	1.50	-1.50	0.00
6,600.0	14.45	24.30	5,646.6	2,730.5	1,232.8	2,995.9	1.50	-1.50	0.00
6,700.0	12.95	24.30	5,743.7	2,752.1	1,242.5	3,019.6	1.50	-1.50	0.00
6,800.0	11.45	24.30	5,841.5	2,771.4	1,251.2	3,040.8	1.50	-1.50	0.00
6,900.0	9.95	24.30	5,939.7	2,788.3	1,258.9	3,059.3	1.50	-1.50	0.00
6,933.8	9.45	24.30	5,973.0	2,793.5	1,261.2	3,065.0	1.50	-1.50	0.00
Top of Gas									
7,000.0	8.45	24.30	6,038.4	2,802.9	1,265.4	3,075.3	1.50	-1.50	0.00
7,100.0	6.95	24.30	6,137.5	2,815.1	1,270.9	3,088.7	1.50	-1.50	0.00
7,200.0	5.45	24.30	6,236.9	2,825.0	1,275.4	3,099.5	1.50	-1.50	0.00
7,300.0	3.95	24.30	6,336.6	2,832.5	1,278.8	3,107.7	1.50	-1.50	0.00
7,400.0	2.45	24.30	6,436.4	2,837.5	1,281.1	3,113.3	1.50	-1.50	0.00
7,500.0	0.95	24.30	6,536.4	2,840.3	1,282.3	3,116.3	1.50	-1.50	0.00
7,563.6	0.00	0.00	6,600.0	2,840.7	1,282.5	3,116.8	1.50	-1.50	0.00
7,600.0	0.00	0.00	6,636.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
7,700.0	0.00	0.00	6,736.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
7,800.0	0.00	0.00	6,836.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
7,900.0	0.00	0.00	6,936.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
8,000.0	0.00	0.00	7,036.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
8,100.0	0.00	0.00	7,136.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
8,200.0	0.00	0.00	7,236.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
8,300.0	0.00	0.00	7,336.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
8,400.0	0.00	0.00	7,436.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
8,500.0	0.00	0.00	7,536.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
8,516.6	0.00	0.00	7,553.0	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
Cameo									
8,600.0	0.00	0.00	7,636.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
8,700.0	0.00	0.00	7,736.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
8,800.0	0.00	0.00	7,836.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
8,900.0	0.00	0.00	7,936.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
9,000.0	0.00	0.00	8,036.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00



**N/A**  
Planning Report

<b>Database:</b>	EDM_PRO	<b>Local Co-ordinate Reference:</b>	Well PA 331-26 - Slot B4
<b>Company:</b>	TEP Rocky Mountain LLC	<b>TVD Reference:</b>	WELL @ 5658.0ft (Original Well Elev)
<b>Project:</b>	Garfield County, CO NAD83	<b>MD Reference:</b>	WELL @ 5658.0ft (Original Well Elev)
<b>Site:</b>	PA 23-26 Pad	<b>North Reference:</b>	True
<b>Well:</b>	PA 331-26	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,100.0	0.00	0.00	8,136.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
9,200.0	0.00	0.00	8,236.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
9,226.6	0.00	0.00	8,263.0	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
<b>RLNS</b>									
9,300.0	0.00	0.00	8,336.4	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
9,379.6	0.00	0.00	8,416.0	2,840.7	1,282.5	3,116.8	0.00	0.00	0.00
<b>PBHL(PA 331-26)</b>									

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
- hit/miss target									
- Shape									
PBHL(PA 331-26)	0.00	0.00	8,416.0	2,840.7	1,282.5	1,617,194.90	2,305,317.90	39° 30' 7.643 N	107° 57' 43.897 W
- plan hits target center									
- Point									

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name		Casing Diameter (in)	Hole Diameter (in)
1,100.0	1,098.8	9 5/8"		9.625	14.750

Formations					
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
2,825.7	2,558.0	Wasatch G		0.00	
2,904.0	2,618.0	Wasatch G Base		0.00	
5,658.6	4,773.0	Ohio Creek		0.00	
5,860.8	4,953.0	Upper MVRD		0.00	
6,933.8	5,973.0	Top of Gas		0.00	
8,516.6	7,553.0	Cameo		0.00	
9,226.6	8,263.0	RLNS		0.00	