

FORM

2

Rev  
08/16

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

401358094

**(SUBMITTED)**

Date Received:

08/01/2017

## APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate
TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_Refilling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: Booth

Well Number: V-8-7HN

Name of Operator: BAYSWATER EXPLORATION AND PRODUCTION LLC

COGCC Operator Number: 10261

Address: 730 17TH ST STE 610

City: DENVER

State: CO

Zip: 80202

Contact Name: Jeff Annable

Phone: (303)928-7128

Fax: (303)218-5678

Email: regulatory@ascentgeomatics.com

## RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20080034

## WELL LOCATION INFORMATION

QtrQtr: SESE Sec: 8 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.498805

Longitude: -104.793338

Footage at Surface: 1246 Feet FNL/FSL FSL 248 Feet FEL/FWL FEL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4807

County: WELD

GPS Data:

Date of Measurement: 03/16/2017 PDOP Reading: 2.1 Instrument Operator's Name: Alan Hnizdo

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL FSL 470 FEL 525 FSL 2170 FEL  
 Sec: 8 Twp: 6N Rng: 66W Sec: 7 Twp: 6N Rng: 66W

## LOCATION SURFACE &amp; MINERALS &amp; RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☒ is the mineral owner beneath the location.(check all that apply) ☒ is committed to an Oil and Gas Lease.☒ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 6 North, Range 66 West, 6th PM  
Section 8: Lot A and B of Recorded Exemption No. 0805-08-4-RE 1835  
Section 8: Lot B of Recorded Exemption No. 0805-08-1-RE 4686

See attached lease map.

Total Acres in Described Lease: 171 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 287 Feet  
Building Unit: 668 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 224 Feet  
Above Ground Utility: 258 Feet  
Railroad: 5280 Feet  
Property Line: 237 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 05/15/2017

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 150 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 470 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

Nearest wellbore permitted or completed in the same formation is the proposed Hergert 8-43 API# 05-123-22693 (NB-CD).

NBRR: Proposed Spacing Unit is described as:  
T6N-R66W:  
Sec 7 - S2SE4  
Sec 8 - S2S2

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		240	GWA

## DRILLING PROGRAM

Proposed Total Measured Depth: 14433 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 56 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE

Drilling Fluids Disposal Methods: Land application

Cuttings Disposal: OFFSITE

Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

Surface Hole: Drilling Fluids and Cuttings will be disposed of through land farming and beneficial reuse at the Harlan Hankins Beneficial Reuse Area.

Production Hole: Drilling Fluids and Cuttings will be disposed of at a commercial disposal location.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: 451005 or Document Number:

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	42	0	80	400	80	0
SURF	13+1/2	9+5/8	36	0	1500	660	1500	0
1ST	8+1/2	5+1/2	20	0	14433	2423	14433	0

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments	<p>Letter to the Director for COGCC Rule 318A.a. Exception Location Request, attached as Exception Loc Request.</p> <p>Waiver for COGCC Rule 318A.a. GWA window, attached as Exception Loc Waiver.</p> <p>Letter to Director for COGCC Rule 318A.e. Proposed Spacing Unit, attached as Proposed Spacing Unit.</p> <p>Nearest permitted or existing wellbore belonging to another operator from a 3D perspective is the Hergert 8-43 API# 05-123-22693.</p> <p>Bayswater will not complete the wellbore at the following measured depths since a 317.s. Stimulation Setback Consent hasn't been obtained from the offset operators:</p> <p>11,300'-11,545' (Hergert 8-33) 10,127'-10,404' (Hergert 8-34) 8,612'-8,891' (Hergert 8-43) 14,204'-14,411' (Schaefer 34-7D)</p>
----------	---

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jeff Annable

Title: Regulatory Analyst Date: 8/1/2017 Email: regulatory@ascentgeomatics.c

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

API NUMBER

05

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

--	--



## Best Management Practices

No	BMP/COA Type	Description
1	Planning	Plugged and abandoned wells will be identified pursuant to 319.a.(5)
2	Emissions mitigation	Green Completions - Emission Control System: Test separators and associated flow lines and sand traps shall be installed to accommodate green completions techniques pursuant to COGCC Rules. Operator is working with midstream operators in the area. Operator will connect to a gas sales line prior to flowback and immediately direct salable quality gas down line. The flowback gas shall be thermally oxidized in an emissions control device (ECD), which will be installed and kept in operable condition for at least the first 90 days of production pursuant to CDPHE rules. This ECD shall have an adequate capacity for 1.5 times the largest flowback within a 10 mile radius, will be flanged to route gas to other or permanent oxidizing equipment, and shall be provided with the equipment needed to maintain combustion where non-combustible gases are present.
3	Odor mitigation	Equipment shall be operated in such a manner that odors and dust do not constitute a nuisance or hazard to public welfare.  Oil and gas operations shall be in compliance with the Department of Public Health and Environment, Air Quality Control Commission, Regulation No. 2 Odor Emission, 5 C.C.R. 1001-4, Regulation No. 3 (5 C.C.R. 1001-5), and Regulation No. 7 Section XVII.B.1 (a-c) and Section XII.
4	Drilling/Completion Operations	A closed-loop system will be used for drilling operations.  Blowout Prevention Equipment ("BOPE"): A double ram and annular preventer will be used during drilling. Stabbing valves shall be installed in the event of reverse circulation and shall be prior tested with low and high pressure fluid.  Bradenhead Monitoring: Operator acknowledges and will comply with COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
5	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with Cased hole Pulsed Neutron Log with Gamma Ray Log from TD into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run in that well and have those logs attached. The Form 5 for each well shall clearly state "No open-hole logs were run" and shall reference the Rule 317.p Exception granted for the well.
6	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.

Total: 6 comment(s)

## Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401358094	FORM 2 SUBMITTED
401361135	OffsetWellEvaluations Data
401361295	DEVIATED DRILLING PLAN
401361301	DIRECTIONAL DATA
401361304	WELL LOCATION PLAT
401361306	MINERAL LEASE MAP
401361310	EXCEPTION LOC WAIVERS
401361312	EXPEDITED APPROVAL REQUEST
401361322	PROPOSED SPACING UNIT
401372677	OPEN HOLE LOGGING EXCEPTION

Total Attach: 10 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

## Public Comments

No public comments were received on this application during the comment period.

