

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: January 31, 2018

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

5. Lease Serial No.
750881007

6. If Indian, Allottee or Tribe Name
SOUTHERN UTE, BIA

7. If Unit or CA/Agreement, Name and/or No.

SUBMIT IN TRIPLICATE - Other instructions on page 2

1. Type of Well <input type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other: COAL BED METHANE		8. Well Name and No. VALENCIA CANYON 32-1
2. Name of Operator CHEVRON USA INC Contact: APRIL E POHL E-Mail: April.Pohl@chevron.com		9. API Well No. 05-067-07659-00-S1
3a. Address 332 ROAD 3100 AZTEC, NM 87410	3b. Phone No. (include area code) Ph: 505-333-1941	10. Field and Pool or Exploratory Area IGNACIO BLANCO
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Sec 32 T33N R11W SWSE 1157FSL 2474FEL 37.057199 N Lat, 108.064804 W Lon		11. County or Parish, State LA PLATA COUNTY, CO

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input checked="" type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.

THIS WELL HAS BEEN PLUGGED AND ABANDONED.

5/30/17

MIRU.

Well pressures: 2.3in tbg.-45 psi, 5.5in csg.-25 psi, BH-0 psi. RU valves, blow well down.

Pressure test tbg to 1200#; test good. Unseat pump.

LD polish rod. TOOH, LD 4ft pony, 71 .75in rod, 4 sinker bars, 4ft guided rod w rod pump.

ND WD, NU BOP.

TOOH, tally, 1 jts, 10ft, 8ft, subs, 26 stds, 7 jts, SN, MA, (61 jts), 2.325in tbg, EOT @1913ft, (.25in capillary string banded to line cut off in 10ft section off loc.)

5/31/17

Check psi on well: no tbg, 5.5in csg.-25 psi, BH-0 psi. Open well.

Round trip 5.5in gauge ring to 1818ft. RIH w 1 11/16in sinker bar to 1946ft; indicating there is no

14. I hereby certify that the foregoing is true and correct. Electronic Submission #378933 verified by the BLM Well Information System For CHEVRON USA INC, sent to the Durango Committed to AFMSS for processing by ASHLEY HITCHELL on 06/27/2017 (17BDT0116SE)	
Name (Printed/Typed) APRIL E POHL	Title AUTHORIZED REPRESENTATIVE
Signature (Electronic Submission)	Date 06/14/2017

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By ACCEPTED	JOHN PECOR Title MINERALS STAFF CHIEF	Date 06/27/2017
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office Durango

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

**** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ****

*EWJ
6/29/17*

Additional data for EC transaction #378933 that would not fit on the form

32. Additional remarks, continued

CIBP. POOH.

Set a CR @1860ft.

PU 5.5in string mill, TIH w 26 stds, PU 6 jts, tag up @1847ft; unable to get to 1860ft

Allen White (CO BLM) approved to set plug 2, continue w plug.

TOH, LD string mill.

PU 5.5in CR, TIH to 1643ft; set CR.

Est circ w 37 BBLs, pumped 45 BBLs total. Attempt to PT csg to 800#; dropped to 50# in 10 mins, no test.

Plug 1 Fruitland top with CR at 1643ft; mix, pump 45 sxs (53.1 cu/ft) 15.8# Class B cement 1643ft to 1237ft TOC.

TOH, LD setting tool.

6/1/17

Open up well; no pressures.

TIH, tag Plug 1 @1320ft; tag good.

Est circ w 2 BBLs, PT csg. to 800#; test good. Pump 35 BBLs of corrosion inhibitor from 1320ft to 0ft.

TOH to 350ft; load, est circ w 1 BBL.

Plug#2, Surface top; mix, pump 55 sxs (64.9 cu/ft) 15.5# Class B cement 350ft to 0ft. LD 11 jts.

ND BOP, NU WH.

RDMO.

Revisions to Operator-Submitted EC Data for Sundry Notice #378933

	Operator Submitted	BLM Revised (AFMSS)
Sundry Type:	ABD SR	ABD SR
Lease:	750881007	750881007
Agreement:		
Operator:	CHEVRON USA 332 ROAD 3100 AZTEC, NM 87410 Ph: 505-333-1941	CHEVRON USA INC 332 ROAD 3100 AZTEC, NM 87410 Ph: 505-333-1941
Admin Contact:	APRIL E POHL AUTHORIZED REPRESENTATIVE E-Mail: April.Pohl@chevron.com Ph: 505-333-1941	APRIL E POHL AUTHORIZED REPRESENTATIVE E-Mail: April.Pohl@chevron.com Ph: 505-333-1941
Tech Contact:	APRIL E POHL AUTHORIZED REPRESENTATIVE E-Mail: April.Pohl@chevron.com Ph: 505-333-1941	APRIL E POHL AUTHORIZED REPRESENTATIVE E-Mail: April.Pohl@chevron.com Ph: 505-333-1941
Location:		
State:	CO	CO
County:	LA PLATA COUNTY	LA PLATA
Field/Pool:	IGNACIO BLANCO	IGNACIO BLANCO
Well/Facility:	VALENCIA CANYON SU 32 0 Sec 32 T33N R11W SWSE 1157FSL 2474FEL 37.057199 N Lat, 108.064804 W Lon	VALENCIA CANYON 32-1 Sec 32 T33N R11W SWSE 1157FSL 2474FEL 37.057199 N Lat, 108.064804 W Lon