

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

401391597

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: JENNIFER THOMAS

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6808

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

API Number 05-123-44407-00

County: WELD

Well Name: BUTTERBALL

Well Number: 25N2-34HZ

Location: QtrQtr: NENW Section: 10 Township: 2N Range: 67W Meridian: 6

Footage at surface: Distance: 820 feet Direction: FNL Distance: 2280 feet Direction: FWL

As Drilled Latitude: 40.157638 As Drilled Longitude: -104.877726

GPS Data:

Date of Measurement: 04/04/2017 PDOP Reading: 1.3 GPS Instrument Operator's Name: ROB WILSON

** If directional footage at Top of Prod. Zone Dist.: 375 feet. Direction: FNL Dist.: 2410 feet. Direction: FEL

Sec: 10 Twp: 2N Rng: 67W

** If directional footage at Bottom Hole Dist.: 2582 feet. Direction: FSL Dist.: 2365 feet. Direction: FEL

Sec: 34 Twp: 3N Rng: 67W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 04/12/2017 Date TD: 06/08/2017 Date Casing Set or D&A: 06/09/2017

Rig Release Date: 07/07/2017 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 16098 TVD** 7314 Plug Back Total Depth MD 16071 TVD** 7314

Elevations GR 4934 KB 4966 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

CBL, GR, CNL RUN ON BUTTERBALL 25C-34HZ, API 05-123-44409

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42	0	112	64	0	112	VISU
SURF	13+1/2	9+5/8	36	0	1,862	723	0	1,862	VISU
1ST	7+7/8	5+1/2	17	0	16,088	1,620	610	16,088	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,439				
SHARON SPRINGS	7,216				
NIOBRARA	7,319				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

Per Rule 371.p Exception, compensated neutron logs have been run on the BUTTERBALL 25C-34HZ well (API 05-123-44409).

Completion for this well is estimated for Q1, 2018.

The Top of Productive Zone provided is an estimate based on the landing point at 7757' MD.

As-drilled GPS data was taken after conductor was set.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: JENNIFER THOMAS

Title: REGULATORY ANALYST

Date: _____

Email: jennifer.thomas@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
401391618	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
401391617	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
401391616	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401391623	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401391624	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401392630	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401392632	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)