

# Construction and Stormwater Inspection

September 7, 2017

Operator: BURLINGTON RESOURCES OIL & GAS LP- #26580

Location ID: 439225

Arapahoe County, CO

SESE Section 8 T4S R64W

Chris Binschus  
Reclamation Specialist, COGCC



**COLORADO**  
Oil & Gas Conservation  
Commission

Department of Natural Resources

**Inspection Photos**  
**Location Name: Tiberius 4-64 8 /4H**  
**Location ID: 439225**



Google Earth imagery taken on June 14, 2016 illustrating the location that was mapped on September 7, 2017 using a Trimble Juno 3B handheld device. GPS data would indicate construction disturbance was exceeded by approximately 2.41 acres (55% overbuilt), totaling 6.76 acres.

Inspection Photos  
Location Name: Tiberius 4-64 8 /4H  
Location ID: 439225



**Photo 1.** Well sign taken at the entrance of location, facing West.



**Photo 2.** Photo taken from the entrance of location, facing North. A culvert installed at the entrance with a stabilized inlet and outlet area.

Inspection Photos  
Location Name: Tiberius 4-64 8 /4H  
Location ID: 439225



**Photo 3.** Photo taken from the entrance of location, facing West. Cattle guard installed at the entrance of location.



**Photo 4.** Photo taken from the eastern location, facing North. Appears topsoil has been salvaged and stored along the eastern and northern well pad perimeters. Topsoil has been mulched with a filter wattle installed around the toe of slope.

Inspection Photos  
Location Name: Tiberius 4-64 8 /4H  
Location ID: 439225



**Photo 5.** Photo taken from the northern location, facing West. Ditch BMP has been installed around well pad perimeter and portions of the outer perimeter.

**Photo 6.** Photo taken from the northwest location, facing West. Ditch BMP that installed around the northern topsoil stockpile ends at a stabilized area made of rip-rap. Filtrexx BMPs have been installed along the northwestern, western, and southern location perimeters.

Inspection Photos  
Location Name: Tiberius 4-64 8 /4H  
Location ID: 439225



**Photo 7.** Photo taken from the northwest location, facing South. Ditch BMP installed around the well pad perimeter is directed to the western sediment trap- see photo 9.



**Photo 8.** Photo taken from the southwest location, facing East. Ditch BMP has been installed around well pad perimeter and portions of the outer perimeter, in addition to filtrex BMP outside of the ditch BMP. A small portion along the southern perimeter outside of the fenced area was not mapped but appeared to be oil and gas disturbances. Ditch and filtrex BMP observed outside the fenced area.

Inspection Photos  
Location Name: Tiberius 4-64 8 /4H  
Location ID: 439225



**Photo 9.** Photo taken from the western sediment trap, facing North. Sediment trap has been installed with a stabilized outlet, in addition to filtrex BMP along the outer perimeter.