

**FORM
INSP**

Rev
X/15

**State of Colorado
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:

09/06/2017

Submitted Date:

09/08/2017

Document Number:

690100094

FIELD INSPECTION FORM

Loc ID 329859 Inspector Name: Maclaren, Joe On-Site Inspection 2A Doc Num: _____

Status Summary:

- THIS IS A FOLLOW UP INSPECTION
- FOLLOW UP INSPECTION REQUIRED
- NO FOLLOW UP INSPECTION REQUIRED

Operator Information:

OGCC Operator Number: 47120
Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP
Address: P O BOX 173779
City: DENVER State: CO Zip: 80217-

Findings:

3 Number of Comments
1 Number of Corrective Actions

Corrective Action Response Requested

Contact Information:

| Contact Name | Phone | Email | Comment |
|--------------------|-------|-------------------------------|---------|
| Schlagenhauf, Mark | | mark.schlagenhauf@state.co.us | |
| | | COGCCinspections@anadarko.com | |
| Hazard, Ellice | | ellice.hazard@state.co.us | |

Inspected Facilities:

| Facility ID | Type | Status | Status Date | Well Class | API Num | Facility Name | Insp Status |
|-------------|------|--------|-------------|------------|-----------|---------------|-------------|
| 250141 | WELL | PR | 05/01/2010 | OW | 123-17944 | GLENS VV 6-14 | EG |

General Comment:

Details of observations made during this field inspection are available in the flowline and idle well sections of this report. Photo's uploaded can be accessed via link(s) at the end of this report.

Inspected Facilities

Facility ID: 250141 Type: WELL API Number: 123-17944 Status: PR Insp. Status: EG

Idle Well

Purpose: Shut In Temporarily Abandoned Reminder: _____

Comment: This well is currently Temporarily Abandoned; Flowline cut off below grade at wellhead. The COGCC form 6 intent to abandon Doc #400737557 was submitted to COGCC on 11/20/2014. Expiration is dated 10/31/2015. Contact COGCC Engineering staff regarding need to resubmit form 6 and the schedule of plugging and abandonment.

Also Note: 326 c. Temporarily Abandoned Wells - All temporarily abandoned wells shall pass a mechanical integrity test. (1) A mechanical integrity test shall be performed on each temporarily abandoned well within 30 days of temporarily abandoning the well.

Corrective Action: _____ Date: _____

Flowline

| | | |
|----|-----------------|------------|
| #1 | Type: Well Site | 1 of Lines |
|----|-----------------|------------|

Flowline Description

Flowline Type: Well Site Size: 2" Material: Carbon Steel
 Variance: _____ Age: _____ Contents: Multiphase

Integrity Summary

Failures: _____ Spills: _____ Repairs Made: _____
 Coatings: _____ H2S: _____ Cathodic Protection: _____

Pressure Testing

Witnessed: _____ Test Result: _____ Charted: _____

COGCC Rules(check all that apply)

1101. Installation and Reclamation 1102. Operations, Maintenance, and Repair 1103. Abandonment

Comment: Form 42 notice of flowlines abandoned Doc #401338503 received by COGCC on 07/12/2017. Date of abandonment completed is shown as 05/24/2017. The well site flowline is disconnected and abandoned/ cut off below grade at wellhead; however, the flowline abandonment does not appear to be completed at the separator inlet. Based on observations during field inspection, the flowline ties in with the Glens 2 (API 123-07522/ Producing Well) underground at/ near the horizontal separator. There is a shallow hand dug hole approximately 2' deep around the flowline riser, not deep enough to complete abandonment of the Glens VV 6-14 flowline.

Corrective Action: Complete the flowline abandonment, remove associated flowline risers and/ or signage at the horizontal separator; Confirm Glens 2 flowline is isolated and not tied into the Glens VV 6-14 (partially) abandoned flowline; and submit written documentation (including available photo's) confirming the flowline abandonment has been completed per COGCC rule 1103; email information to COGCC Engineering Integrity staff. Date: 10/09/2017

Attached Documents

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

| Document Num | Description | URL |
|--------------|--|---|
| 401398687 | INSPECTION SUBMITTED | http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4247103 |
| 690100095 | Wellhead and signage; flowline disconnected | http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4247090 |
| 690100096 | Signage on flowline riser at separator inlet | http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4247091 |
| 690100097 | Flowline riser; hand dug hole around riser | http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4247092 |

| | | |
|-----------|--------------------------------|---|
| 690100098 | Glens 2 wellhead/ Producing | http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4247093 |
|-----------|--------------------------------|---|