



Operator: SRC Energy
Well Name: Wolfson #26-16
Legal: SESE, Section 26, Township 4N, Range 67W
Location: Weld County, CO
API: 05-123-14511

Deepest Water Well Within 1
Mile = 70'

Wellbore History

Spud Date: 12/23/1989
Surf Csg: 8.625", 24# @ 232' - 200 sx
Prod Csg: 4.5", 12.6# @ 7367' - 225 sx
TOC: 6150' (CBL)
Perfs: NIO-CODELL: 6889' - 7212'

P&A Procedure

Set CIBP @ 6810'
Set 12 sx on top of retainer (120' plug)
Shoot Circ Holes 4700' and 4300'
Set retainer @ 4325'
Circ 78 sx thru retainer, spot 3 sxs above
Cut Casing @ 282'
Pmp 150 sx @ 332' to surface

Key

 Existing Cement Coverage

 Retainer Cement Pumped