

US ROCKIES REGION
Operation Summary Report

Well: **MATHISEN JAMES H "B" #1**

Spud date: 8/20/1973

Project: COLORADO-WELD-NAD83-UTM13

Site: MATHISEN 19-12 PAD

Rig name no.: CONCORD 4/4

Event: ABANDONMENT

Start date: 7/27/2017

End date: 8/31/2017

Active datum: RKB @4,943.99usft (above Mean Sea Level)

UWI: 0/1/N/67/W/12/O/SWSW/6/PM/S/990.00/W/0/990.00/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
7/14/2017	7:00 - 8:00	1.00	ABANDP	53	B	P		FORM 17 TEST
7/21/2017	-							
7/26/2017	14:30 - 15:30	1.00	ABANDP	30	A	P		MOVE IN EQUIPMENT, HELD JAS MEETING, SPOT IN EQUIPMENT AND RU
	15:30 - 16:30	1.00	ABANDP	30	E	P		RU PUMP LINES, BLOW DOWN WELL TO WORK TANK, KILL WELL WITH 80BBLS,
	16:30 - 17:30	1.00	ABANDP	30	F	P		ND WH, NU BOP'S/WF, GET TBG TONGS READY TO TOOH,
	17:30 - 20:00	2.50	ABANDP	31	I	P		TOOH SB TBG AND TALLY, TOTAL OF 250 JNTS,
	20:00 - 20:30	0.50	ABANDP	30	G	P		CLOSE WELL, SDFN, CT TO YARD
7/27/2017	6:00 - 7:00	1.00	ABANDP	30	G	P		CT TO LOC, HELD JSA MEETING, REFER TO SAFETY TAB, CHECK WELL PRESSURE, 200/0/0PSI,
	7:00 - 7:30	0.50	ABANDP	30	E	P		RU PUMP LINES, BLOW DOWN WEL TO TANK, START PUMP AND KILL WELL W/ 45BBLS H2O/BIO, OPEN WELL
	7:30 - 11:00	3.50	ABANDP	31	I	P		PU 4.5 CSG SCRAPER GO DOWN TO 7870', CHANGE OVER TBG TONG AND TOOH, LD TOOLS,
	11:00 - 11:30	0.50	ABANDP	34	I	P		MIRU WL , HELD JSA MEETING, REFER TO SAFETY TAB, RU TOOLS
	11:30 - 13:30	2.00	ABANDP	34	I	P		MIRU WL, PU 4.5 CIBP, RIH & SET PLUG @ 7860', POOH, PU DUMP BAILER & DUMP 2SX OF CMT ON TOP OF CIBP @ 7860', POOH PU 2ND CIBP, RIH & SET PLUG @ 7434', POOH, RD WL,
	13:30 - 14:30	1.00	ABANDP	31	I	P		PU XN NIPPLE, TIH DOWN TO 3500', RU PUMP LINE
	14:30 - 15:30	1.00	ABANDP	31	H	P		START PUMP AND ROLL ALL GAS OUT,
	15:30 - 16:30	1.00	ABANDP	31	I	P		GET TBG TONG READY AND TOOH SB TBG TO THE DERRICK
	16:30 - 18:30	2.00	ABANDP	34	N	P		RU WL, PU LOGGING TOOLS, RIH AND LOG FROM 7434' TO 0' , SEND LOGS TO THE OFFICE, RDMO CLOSE WELL
	18:30 - 19:00	0.50	ABANDP	30	G	P		CT TO YARD
7/31/2017	6:00 - 7:00	1.00	ABANDP	30	G	P		CT TO LOC, HELD JSA MEETIGN, REFER TO SAFETY TAB, OPEN WELL,
	7:00 - 7:30	0.50	ABANDP	31	H	P		RU PUMP LINES, LOAD WELL AND PRESSURE TEST TO 500PSI, HELD PRESSURE FOR 15 MIN
	7:30 - 9:00	1.50	ABANDP	34	I	P		MIRU WL , RU TOOLS, WAIT FOR WL TO BRING MORE PERF GUNS,
	9:00 - 10:30	1.50	ABANDP	34	H	P		PU 3 1/8 PERF GUNS, 2' & 4', RIH AND SHOOT NIO SQZ HOLES @ 7200' & 6750', POOH RDMO WL
	10:30 - 13:00	2.50	ABANDP	31	I	P		PU 4.5 CICR, RIH AND SET CICR @ 6786',
	13:00 - 15:00	2.00	ABANDP	31	H			RU PUMP LINES & CIRCULATE FOR 3RHS
	15:00 - 15:30	0.50	ABANDP	51	E	P		MIRU O-TEX , HELD JSA MEETING, RU CMT LINE & PRESSURE TEST TO 2500PSI,
	15:30 - 16:30	1.00	ABANDP	51	A	P		PUMP NIO SQZ, 155SX @ 13.5PPG, 1.66YIELD, 45.8BBLS OF CMT, UNDERDISPLACE 3BBLS AND STING OUT OF CICR RDMO O-TEX
	16:30 - 17:30	1.00	ABANDP	31	H	P		PUH TO 6500', RU PUMP LINES, ROLL HOLE CLEAN
	17:30 - 19:00	1.50	ABANDP	31	I	P		GET TBG TONGS READY AND TOOH W/ ALL TBG
	19:00 - 19:30	0.50	ABANDP	30	G	P		CLOSE WELL, CT TO YARD

US ROCKIES REGION
Operation Summary Report

Well: MATHISEN JAMES H "B" #1

Spud date: 8/20/1973

Project: COLORADO-WELD-NAD83-UTM13

Site: MATHISEN 19-12 PAD

Rig name no.: CONCORD 4/4

Event: ABANDONMENT

Start date: 7/27/2017

End date: 8/31/2017

Active datum: RKB @4,943.99usft (above Mean Sea Level)

UWI: 0/1/N/67/W/12/O/SWSW/6/PM/S/990.00/W/0/990.00/O/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
8/1/2017	7:00 - 8:00	1.00	ABANDP	30	G	P		CT TO LOC HELD JSA MEETING, REFER TO SAFETY TAB, OPEN WELL,
	8:00 - 8:30	0.50	ABANDP	34	1	P		MIRU WL, PU TOOLS AND HELD SAFETY METTING,
	8:30 - 9:30	1.00	ABANDP	34	H	P		PU 3 1/8 PERF GUNS, RIH AND SHOOT SQZ HOLES @ 4580' & 4300', POOH, RDMO WL,
	9:30 - 11:00	1.50	ABANDP	31	I	P		GET TBG TONGS READY TO TIH, PU 4.5 CICR, TIH AND SET CICR @ 4332',
	11:00 - 12:00	1.00	ABANDP	31	H	P		RU PUMP LINES, BREAK CIRC & ROLL HOLE FOR 45 MIN 105BBLs,
	12:00 - 12:30	0.50	ABANDP	51	E	P		MIRU O-TEX, HELD JSA MEETING, RU CMT LINE AND PRESSURE TEST TO 2500PSI,
	12:30 - 13:30	1.00	ABANDP	51	A	P		PUMP 140SX @ 15.8PPG 1.16YILED, TOTAL OF 29BBLs OF CMT, UNDERDISPLACE 3BBLs, STING OUT AND RELEASE PRESS, RDMO O-TEX
	13:30 - 14:00	0.50	ABANDP	31	I	P		GET TBG TONGS READY AND PUH TO 4000',
	14:00 - 15:00	1.00	ABANDP	31	H	P		RU PUMP LINES, ROLL HOLE CLEAN, FOR 1HR, RD PUMP LINES
	15:00 - 16:30	1.50	ABANDP	31	I	P		RU TBG TONGS AND TOOH, LD TOOLS
8/2/2017	16:30 - 17:30	1.00	ABANDP	30	G	P		CLOSE WELL, PU LOC, CT TO YARD
	6:00 - 7:00	1.00	ABANDP	30	G	P		CT TO LOC, HELD JSA MEETING, REFER TO SAFETY TAB, OPEN WELL,
	7:00 - 7:30	0.50	ABANDP	34	1	P		MIRU WL, HELD SAFETY MEETING, TALK ABOUT TRIP, FALL, PINCH POINTS, OVER HEAD LOEADS AND EXPLOSIVES, RU TOOLS,
	7:30 - 8:30	1.00	ABANDP	34	H	P		PU 3 1/8 PERF GUNS, RIH & SHOOT HOLES @ 1508' & 800', POOH RDMO WL,
	8:30 - 10:00	1.50	ABANDP	31	I	P		PU 4.5 CICR, RIH & SET IT @ 830'
	10:00 - 12:00	2.00	ABANDP	31	H	P		RU PUMP LINES, PUMP 135BBLs OF WATER TO ROLL HOLE,
	12:00 - 12:30	0.50	ABANDP	51	E	P		MOVE IN & SPOT IN SLB EQUIPMENT, HELD JSA MEETING, RU CMT LINE,
	12:30 - 13:30	1.00	ABANDP	51	A	P		PUMP FOX HILLS SQZ, 253SX @ 15.8PPG, 1.50YIELD, UNDERDISPLACE 3BBLs & STING OUT CICR, RD CMT LINE
	13:30 - 14:00	0.50	ABANDP	31	I	P		PUH TO 300', LD JOINTS ON TBG TRAILER
	14:00 - 14:30	0.50	ABANDP	51	D	P		RU CMT LINE, BREAK CIRCULATION, PUMP STUB PLUG, 38SX @ 15.8PPG 1.52YILED, RD CMT
8/3/2017	14:30 - 15:00	0.50	ABANDP	31	H	P		PUH TO 96' AND ROLL HOLE CLEAN, RDMO SLB, TOOH,
	15:00 - 15:30	0.50	ABANDP	30	G	P		CLOSE WELL, SDFN, CT TO YARD
	6:00 - 7:00	1.00	ABANDP	30	G	P		CT TO LOC, HELD JSA MEETING, REFER TO SAFETY TAB,
	7:00 - 7:30	0.50	ABANDP	34	1	P		SPOT IN WL, RU EQUIPMENT
	7:30 - 8:00	0.50	ABANDP	34	G	P		PU WEIGHT BAR, RIH AND TAG TOC @ 50', POOH
	8:00 - 8:30	0.50	ABANDP	34	I	P		PU 4.5 CIBP, RIH AND SET PLUG @ 40', POOH RDMO WL,
	8:30 - 9:30	1.00	ABANDP	30	C	P		PU LOC, RDMO CONCORD 4, PU PUMP LINES & GET ALL EQUIPMENT READY TO MOVE TO NEXT LOC,
	6:00 - 7:00	1.00	ABANDZ	52		P		PRESSURE TESTED CIBP, 4-1/2 CASING TO 500 PSI
	7:00 - 8:00	1.00	ABANDZ	53	B	P		DUG UP SURFACE CASING
	8:00 - 9:00	1.00	ABANDZ	53	C	P		CUT CASINGS 6' BELOW GL. TAGGED @ 40' IN 4-1/2, 180' IN 8-5/8

US ROCKIES REGION
Operation Summary Report

Well: MATHISEN JAMES H "B" #1				Spud date: 8/20/1973				
Project: COLORADO-WELD-NAD83-UTM13			Site: MATHISEN 19-12 PAD				Rig name no.: CONCORD 4/4	
Event: ABANDONMENT			Start date: 7/27/2017				End date: 8/31/2017	
Active datum: RKB @4,943.99usft (above Mean Sea Level)				UWI: 0/1/N/67/W/12/O/SWSW/6/PM/S/990.00/W/0/990.00/0/0				
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	9:00 - 10:00	1.00	ABANDZ	53	B	P		FILLED 4-1/2 WITH 6 BAGS, 8-5/8 WITH 32 BAGS 5000 PSI CEMENT
	10:00 - 11:00	1.00	ABANDZ	53	A	P		CAPPED CASING WITH A METAL PLATE CONTAINING WELL INFO
	11:00 - 11:00	0.00	ABANDZ	53	F	P		DROPPED MARKER BALL
	11:00 - 12:00	1.00	ABANDZ	53	B	P		BACKFILLED
	11:00 - 11:00	0.00	ABANDP	50		P		P&A'd OFFLINE. CD/J.