# *PADCO LLC*

## WELLBORE SCHEMATIC - Proposed Plugging

***Well :*** **Bacon Unit 1** ***API #:*** **05-121-10647**
***Field :*** **East Woodrow (#43900)**
***Category :*** **Vertical**
***County :*** **Washington** ***State :*** **Colorado**
***Legal Location :*** **SW NE Sec. 28-T1S-R55W** ***GPS Location :*** **(Lat. 39.93795N, Long. 103.54474W )**
***Producing Formation :*** **D Sand**
***Elevation :*** **KB = 4556', GL = 4546'**

FORMATION TOPS | CASING PROGRAM




10 sxs top plug to surface

Surface Csg Bit size 12 1/4"

8 5/8", 25#, set @ 150' w/ 75 sxs; cement to surface

50 sxs half-in, half-out from 200 ft. to 100 ft.

***Proposed to pull csg from approximately 3000'***




Top of Cement @ 3540'

**Set CIBP @ 4840' w/ 2 sxs**

Perfs: 4875-4882' (4 SPF)

5 1/2", 14# & 15.5# Production Casing @ 5020' w/ 150 sxs